# ATLANTIC CANADA STUDY

Building Structure Cost Comparison

# MULTI-RESIDENTIAL STRUCTURES



**Study Sponsored by:** 







#### DISCLAIMER

The primary responsibility of the Canada Masonry Design Centre is to encourage the effective use of masonry through research, education and technical support. This study was developed to assist the designer and developer in understanding loadbearing masonry, how it compares to current construction practices, and how to build effectively with masonry. The discussion, costing data, and design recommendations are intended to assist with the beginning steps of a loadbearing masonry project.

The material presented does not cover all possible situations but is intended to represent some of the more common construction practices in Atlantic Canada. These construction practices, as well as building code requirements, can vary significantly in different localities. For this reason, the information contained in this study is of a general nature and represent design conditions, assumptions and procedures that are common in Atlantic Canada during the time the study was completed. The actual design of a loadbearing masonry building, preparation of working drawings, and similar tasks should be completed by a qualified architect or engineer familiar with local conditions and code requirements.

Care has been taken to ensure that the information included in this study is as accurate as possible. However, CMDC does not assume responsibility for errors or omission resulting from the use of this study.

#### Copyright © 2020 Canada Masonry Design Centre

Loadbearing Study Lead Writers:

Andrew H. Smith, M.A.Sc., E.I.T. – Masonry Design Coordinator Bennett R. Banting, PH.D., P.Eng. – Director of Technical Services, Engineered Masonry

#### **CMDC Technical Team**

 David Stubbs, P.Eng. – Executive Director of the Canada Masonry Centre Joe Wierzbicki, M.A.Sc., P.Eng. – Masonry Design Engineer
 Sasha Kisin M.A.Sc., P.Eng. – Masonry Design Engineer
 Monica Guzman M.Sc., P.Eng. – Masonry Design Engineer
 Brad Crumb, P.Eng. – Masonry Design Engineer



Published by:

Canada Masonry Design Centre 360 Superior Blvd. Mississauga, ON L5T 2N7 http://www.canadamasonrydesigncentre.com/

## **Table of Contents**

Executive Summary
Introduction
Study Objectives
Study Methodology
Background6
Model Building Architype6
Building Design Options7
Study Results and Discussion
Building Structure Costs
Total Finished Building Costs10
Masonry Benefits justify a small Premium11
Exceeding Code Minimums11
Comparing Fire Ratings for the Building Designs11
Superior Sound-Proofing12
Additional Benefits13
Masonry Friendly Design
Timing of Construction14
Continuity of Loadbearing Walls14
Spacing Between Walls14
Wall Location and Orientation15
Comparison to a Previous Study
Construction Location
Scope of Study16
Building Layout16
Conclusion
References
APPENDIX A – Floor Layout
APPENDIX B – Construction Schedule
APPENDIX C – Structural Drawings 28

### **Executive Summary**

A comparison of construction costs between loadbearing masonry, cast-in-place concrete and wood frame construction was undertaken for a prototype multi-residential building typical of Atlantic Canada. The city of Moncton, NB was selected, and a full design, scheduling and cost analysis was conducted by third-party firms. As a result, when the cost of the structure alone is compared, masonry was 11% more costly than wood frame in the building option with a parking garage and 24% more costly in the building option with a slab-on-grade. When considering the total (approximate) hard costs for the whole building loadbearing masonry was only 4% more expensive than the wood frame option in the building with an underground parking garage and 8% more expensive for slab-on-grade.

This nominal cost difference did not account for the added benefits associated with using masonry materials such as increased fire ratings, a non-combustible building structure, added sound insulation properties and reduced maintenance costs associated with a more durable building. Nor does this cost comparison account for relative cost differences that might occur if a masonry veneer had been selected and priced, if minor modifications to the wall layout were made to make it a more masonry friendly design and if a full architectural design for sound and fire was made. Total building cost was conservatively determined and applied equally to all materials in a manner that would be more punitive for the masonry option. Regardless, an upper bound 4% price differential (close to the cost difference determined in a previous study of 5%) supports the idea that developers can enjoy the plethora of benefits associated with concrete block masonry buildings for what is in effect a nominal cost increase from wood frame.

### Introduction

Atlantic Canada has a demand for multi-residential structures. The reason for this demand is due to increasing populations (mostly through immigration<sup>1</sup>), increases in student populations at universities<sup>2</sup> (especially international students), and current vacancy rates on apartment rentals are some of the lowest in the country<sup>2</sup>.

City	Private Apartment Vacancy Rate (%)
Halifax	0.9%
Moncton	2.4%
Charlottetown	1.2%
Fredericton	1.4%

Table 1 Vacancy Rates by Atlantic Canada City (2019)<sup>2</sup>

The increase in demand for rental units led to an increase in multi-residential construction. This, in turn, led to an increase in units under construction which continues to be matched by further increases in demand. Since the opening of the Atlantic Canada CMDC office we have received comments from the community on how the current building construction methods for multi-residential construction are limited in their ability to match the increase in demand, which are summarized below.

- Wood frame construction is typically limited by building code limitations as well as perceived and quantifiable concerns about its resilience and durability.
  - Regions in Atlantic Canada under the 2010 National Building Code of Canada (NBCC) are limited to 4storeys for wood construction, while regions under the 2015 NBCC are limited to 6-storeys for wood construction.
  - Wood frame construction achieves fire and sound resistance via insulation and gypsum board products. This can often require complex detailing and may lead to long-term maintenance costs.
  - Wood frame construction is generally viewed as being less durable and resilient when compared to concrete and masonry construction, which has numerous built-in redundancies.
  - Moisture, specifically, is associated with long-term issues in wood frame construction due to differential movement, mould growth, susceptibility to pests and structural damage.
- **Cast-in-place concrete** construction is typically limited by workforce as well as construction costs.
  - Concrete finishers are relied upon in high-rise and commercial construction, which may take priority over relatively smaller residential projects. Delays or changes in demand in these other sectors have a trickle-down effect on low- and mid-rise residential construction schedules.
  - Increasing costs for concrete construction is one of the main reasons why developers have sought out other material options for multi-residential construction.

This study was developed in response to comments made from developers indicating the desire to upgrade to a non-combustible and more robust building material than conventional wood framing but without the significant increase in cost associated with cast in-place concrete construction. The purpose of this cost study is to introduce a new option for developers to consider. This study demonstrates that a **Loadbearing Masonry** structure provides developers with a building material that is non-combustible, low maintenance, and greater durability with a low initial cost of construction. It also pulls from a workforce that is not currently backlogged in the multi-residential market, and masonry can be constructed with an overall cost comparable to wood frame construction, as will be demonstrated.

## **Study Objectives**

The objective of this study was to develop a cost model to evaluate the relative cost of construction for a mid-rise multi-residential building. The study investigated the relative costs using three different building materials and two model building options (with and without underground parking). The units in the model buildings are a typical size and layout as observed in recent construction within Atlantic Canada for apartments, condominiums and student housing amongst others.

In doing the cost analysis, this study sets out to quantify and demonstrate two main points:

- 1. Loadbearing masonry is a more cost-effective method of non-combustible construction than cast in-place concrete.
- 2. Loadbearing masonry provides all the added benefits (resiliency, durability, etc.) associated with non-combustible construction (e.g. cast-in-place concrete) without a significant increase in cost compared to conventional wood frame construction.



Figure 1 – Unit demising walls built out of loadbearing masonry provide excellent fire rating and sound proofing as well as being the main structural element of the building.

## **Study Methodology**

#### **Background**

According to city by-laws in Moncton NB, the model building archetype analyzed in this study were designed to the code requirements of the **2010 National Building Code of Canada**. The chosen floor layouts and room sizes are typical for new construction in Atlantic Canada.

The 3<sup>rd</sup> party design team for this study is comprised of:

Architectural Design: Spitfire Design Co.

Structural Analysis and Engineering: Valron Engineers Inc. a Gemtec Company

Cost and Timeline Estimation: Acadian Construction

**Spitfire Design Co.** is based out of Moncton, NB and is an interdisciplinary design firm, specializing in architectural design and design coordination of multi-unit buildings, restaurants and custom homes.

**Valron Engineers Inc. a Gemtec Company** is a civil engineering firm based out of Moncton, NB that specializes in structural engineering with extensive experience in design of structural steel, reinforced and prestressed concrete, masonry, timber and aluminum.

**Acadian Construction** is a locally owned private firm founded in 1958 that offers contracting and project management services in the institutional, retail, restaurant, office, commercial, light industrial, hotel and multi-residential sectors. They have experience building in Moncton, NB with both wood and concrete in the multi-residential sector.

**Sponsors**: This study is funded and supported through a collaborative effort by the Atlantic Masonry Institute (**AMI**), Canada Masonry Design Centre (**CMDC**) and Canadian Concrete Masonry Producers Association (**CCMPA**). Authorship of this report was carried out by the engineering staff at Canada Masonry Design Centre. The views and conclusions drawn within this report are solely those of AMI, CMDC and CCMPA. The 3<sup>rd</sup> party design team were not responsible for the body of the report and the additional conclusions and analysis drawn. The work of the 3<sup>rd</sup> party design team is presented within the appendices and distillation of the results are reported herein.

#### **Model Building Architype**

The building model used for the cost analysis was a 4-storey, 55-unit building with a rectangular footprint of just under 15,000 sq. ft located in Moncton, NB. The building consists of 11 One-Bedroom units, 28 interior Two-Bedroom units, and 16 corner Two-Bedroom units with floor areas of 759 sq. ft, 1,069 sq. ft, and 1,177 sq. ft respectively. The starting schematic floor plan used for each design can be found in **Appendix A**.

It was decided that for the purpose of this study, to compare costs for ONLY the building structure (and enclosure). The choices for building façade, interior finishes, electrical and HVAC were omitted in order to provide a true comparison for the chosen structural system alone.

It should be noted that the chosen building layout does not reflect the most cost-effective layout for any single option. The layout was chosen based on what would be seen in a "typical" construction in Atlantic Canada, after which each option was adapted to work with the chosen layout. For the most successful loadbearing masonry project, see the suggestions found in the section: **Masonry Friendly Design**. This section provides design strategies to help optimize the building layout for loadbearing masonry.

### **Building Design Options**

The following buildings were designed and evaluated for construction timelines and costs:

- 1A Conventional wood framing and a wood floor system with underground parking
- 1B Conventional wood framing and a wood floor system with a slab-on-grade
- **2A** Loadbearing concrete masonry construction with precast hollowcore plank flooring system and underground parking
- **2B** Loadbearing concrete masonry construction with precast hollowcore plank flooring system with a slab-on-grade
- **3A** Cast in-place reinforced concrete construction with underground parking
- **3B** Cast in-place reinforced concrete construction with a slab-on-grade

Both loadbearing concrete masonry and cast in-place reinforced concrete buildings used light weight - 6 in. steel stud framing to enclose the building while the conventional wood construction used 2×6 in. dimensional lumber.

For the purposes of this study, model buildings both with and without underground parking were examined. Atlantic Canada has a larger variation from city-to-city with regards to population density. For example, a theoretical building in Halifax would have a much higher \$/unit cost for an outdoor parking lot instead of underground parking. Alternatively, a building located in Dieppe may show savings in \$/unit by doing a parking lot rather than underground parking. Loadbearing masonry can be a viable option for all multi-residential structures, and is not limited by the proposed location.



Figure 2 - Loadbearing masonry walls can be used for interior and exterior walls.

## **Study Results and Discussion**

#### **Building Structure Costs**

The results for the construction cost study for the building **with underground parking (A)** and the building **with a slab-on-grade (B)** are presented in the tables below for the three different building materials as well as the construction timelines associated with erecting the building structure for each option.

Building System	Cost	Timeline
1A-Conventional Wood Framing	\$3,709,807	42 Weeks
2A-Loadbearing Masonry	\$4,390,216	28 Weeks
3A-Cast in-Place Concrete	\$5,321,922	46 Weeks

#### Table 2 Construction Costs with Underground Parking (Structure Only)

#### Table 3 Construction Costs for Buildings with a Slab-on-Grade (Structure Only)

Building System	Cost	Timeline
1B-Conventional Wood Framing	\$2,817,531	36 Weeks
2B-Loadbearing Masonry	\$3,711,967	26 Weeks
3B-Cast in-Place Concrete	\$4,406,129	42 Weeks

The results in **Table 2 and 3** confirms the information and concerns expressed to CMDC by developers in Atlantic Canada: conventional wood framing is the cheapest initial cost option. However, this would be expected as loadbearing masonry has added durability, resiliency, soundproofing, and fire-resistance properties that will be further examined in the **Masonry Benefits justify a small Premium** section later on in the document. That is to say, all options meet code minimums, but masonry and concrete generally meet and exceed many of these minimums without any additional special detailing otherwise required for wood frame construction.

When a developer is looking to finance the construction of a multi-unit residential building, a building that opens quicker brings in money quicker. *Not only does an accelerated timeline allow for additional rent payments, but there are many other equally important costs to consider during the construction phase (builders risk insurance, interest on financing, etc.).* 

When scheduled correctly (preferably not during winter conditions) loadbearing masonry was determined to have an accelerated timeline when compared to concrete and wood construction. Not only does the structure go up fast, but since the hollowcore planks do not require shoring, it allows for other trades to mobilize immediately so that electrical, mechanical, enclosures and partitions be installed while work on the structure above continues. Gantt Charts detailing the construction schedules that support this conclusion can be found in **Appendix B**.

**Tables 4 and 5** compare the construction completion times for loadbearing masonry relative to conventional wood framing (1a and 1b), and Cast in-place Concrete (3a and 3b) respectively. The last column in the table is denoted as **"Loss of Rental Income"** which represents the rental income lost for the

building based on an assumed rental revenue of \$1.30/sq. ft and a 2% vacancy rate over the difference in construction timelines. These rent statistics represent typical values confirmed by **Spitfire Design Co**.

Building System	Timeline	Additional Time to Completion (vs. Masonry)	Loss of Rental Income
1A-Conventional Wood Framing	42 Weeks	+14 Weeks	\$246,636
2A-Loadbearing Masonry	28 Weeks	-	-
3A-Cast in-Place Concrete	46 Weeks	+18 Weeks	\$317,104

Table 4 Construction Completion Time and Loss of Rental Income for Buildings with Underground Parking

 Table 5 Construction Completion Time and Loss of Rental Income for Buildings with Slab-on-Grade

Building System	Timeline	Additional Time to Completion (vs. Masonry)	Loss of Rental Income
1B-Conventional Wood Framing	36 Weeks	+10 Weeks	\$176,169
2B-Loadbearing Masonry	26 Weeks	-	-
3B-Cast in-Place Concrete	42 Weeks	+16 Weeks	\$281,870

The dollar values for the "Loss of Rental Income" are substantial and should be considered as a part of the building structure material selection process. In an effort to show the impact that scheduling can have on costs, **Table 6 and 7** take the building construction costs and add in the "Loss of Income" from the construction schedule as an added expense to conventional wood framing and cast in-place concrete. Costs are then normalized to wood frame (1A and 1B) and presented as a relative cost.

Table 6 Cost Comparison with Rental Income for Buildings with Underground Parking (Structure Only)

Building System	Cost	Relative Cost
1A-Conventional Wood Framing	\$3,956,444	100
2A-Loadbearing Masonry	\$4,390,216	111
3A-Cast in-Place Concrete	\$5,639,027	143

Table 7 Cost Comparison with Rental Income for Buildings with Slab-on-Grade (Structure Only)

Building System	Cost	Relative Cost
1B-Conventional Wood Framing	\$2,993,700	100
2B-Loadbearing Masonry	\$3,711,967	124
3B-Cast in-Place Concrete	\$4,688,000	157

With rental income in mind loadbearing masonry comes at only an 11% cost premium to conventional wood framing for the building structure alone (in the building option with underground parking).

### **Total Finished Building Costs**

By the time the building is finished, how much will the choice of structural material affect the final construction cost? The cost for the remainder of the building will be highly dependent on many other hard and soft construction costs (e.g. HVAC system, veneer, landscaping, land acquisition, interior furnishings, marketing, etc.). Generally, the costs associated with finishing the building after the structure is erected is constant and does not vary based on the choice of structural material. Depending on those hard and soft costs for the type and location of the building, the associated cost of erecting the loadbearing building structure may account for approximately 15%-50% of the total building costs.

For the following analysis, since the total hard and soft costs are not known, the following assumptions are conservatively made for a fair comparison between structural material selection:

- 1. The building structure (and enclosure) accounts for 40% of the total building costs.
- 2. Total building costs (aside from structure) are constant for all materials.

Then, based on this assumption the building options with underground parking would have a total additional cost of  $\approx$ \$6,585,000. Whereas, building options with a slab-on-grade would have a total additional cost of  $\approx$ \$5,568,000.

The assumption that the cost to finish the building is constant between structural materials **is actually a conservative estimate and punitive to masonry structures**. Due to the inherent fire-resistance and sound-resistant properties of loadbearing masonry and hollowcore floor planks, minimal-to-no additional detailing is needed to meet fire or sound resistance requirements. Nevertheless, ignoring these benefits to masonry and adding total building costs to the data presented in **Tables 5 and 6**, a true comparison for total building costs between the structural materials can be inferred.

Building System	Cost	Relative Cost
1A-Conventional Wood Framing	\$10,541,444	100
2A-Loadbearing Masonry	\$10,975,542	104
3A-Cast in-Place Concrete	\$12,224,027	116

#### Table 8 Finished Building Cost with Underground Parking (Total Building)

#### Table 9 Finished Building Cost with Slab-on-Grade (Total Building)

Building System	Cost	Relative Cost
1B-Conventional Wood Framing	\$8,561,700	100
2B-Loadbearing Masonry	\$9,279,918	108
3B-Cast in-Place Concrete	\$10,256,000	119

Therefore, by the time one of these building options with underground parking is complete and ready for occupancy, loadbearing masonry would come at only a 4% premium over wood frame construction.

## **Masonry Benefits justify a small Premium**

With the results from this cost comparison, a loadbearing masonry building comes with only a small cost premium. The detailed analysis and design found that for structure alone, loadbearing masonry was only an 11% increase in cost. By using the conservative assumption that the cost of completion is equal regardless of building material, loadbearing masonry is expected fall anywhere between equal price and a 4% premium. This section will look at the differences between wood construction and loadbearing masonry construction to determine what exactly a developer gets for this minimal price premium. For reference, full details of the structural designs including foundations, flooring systems, loadbearing walls, and building enclosure, are in **Appendix C**.

#### **Exceeding Code Minimums**

The National Building Code of Canada serves to ensure that all buildings constructed meet a minimum level of safety. The nuances of the building code and its requirements can be argued over by engineers and bureaucrats and inevitably changes from time to time. However, what does not change is that the building code is simply a minimum. Meaning that, if there is a fire in any building, occupants should have enough time to safely exit the building and (hopefully) firefighters have enough time to contain the fire. However, not all materials behave the same under fire conditions and **a fire in a wood frame structure is different from a fire in a masonry structure**.

Masonry and concrete are defined by the National Building Code of Canada as **Non-Combustible Materials**. That means they cannot add fuel to the fire. Masonry will heat up in a fire and after a fire has stopped it may show light spalling over time, but under even extreme fire testing they do not collapse and they do not combust. By contrast, wood frame construction can achieve similar "fire ratings" to masonry and concrete and meet code minimums for fire endurance (e.g. 1-hour fire rating) but they do not have the same fire performance.

Wood is combustible, once a fire has reached a time or even an intensity that exceeds its rating there is no code provision to prevent it from collapse and spreading the fire. **There is no built-in redundancy or resilience**. Observations of fire tests demonstrate that wood frame walls subject to fire hose streams will fall apart like paper<sup>3</sup>, wood floor systems can collapse (risking firefighter safety<sup>4</sup>) and although residents have time to get to safety (the code minimum is achieved), all of their possessions and their home itself can be a complete loss.

By contrast, masonry provides what is known as "passive fire resistance." Masonry walls separate and compartmentalize fires, containing them into the area where they start. Fires that exceed the time or intensity used to assess their code "rating" do not lead to collapse and in most cases have no discernable impact to users outside of where the fire starts in the building. Life safety is achieved, and property damage is mitigated with masonry. This is why many wood frame structures still require non-combustible materials, such as masonry fire walls, in certain locations because of their proven structural resilience and passive fire resistance properties.

#### **Comparing Fire Ratings for the Building Designs**

A fire rating is a prescribed amount of time that a wall system can resist a "standard fire" based on laboratory testing. Failure of a wall is defined as either degradation of the wall (smoke can pass through) or by temperature change on the "cold side" of the wall. The fire-resistance requirements for the building in this study is found under the National Building Code of Canada (NBCC) 2010 Cl. 3.2.2.52 where it states that floor assemblies and loadbearing walls shall require a 1-hour fire-resistance rating.

With conventional wood frame construction, the structural floor assembly is a 14 in. Open Web Wood Joist spaced at 19.2 in. o.c. with a 5/8 in. plywood top and R-20 Batt Insulation. To achieve a 1-hour fire resistance rating on this floor assembly by following the Table 9.10.3.1-B in NBCC, detail F25d would be required. This detail would require the following:

- Batt Insulation must be fibre processed from rock or slag
- Steel furring channels spaced at 600 mm o.c.
- 2 layers of 15.9 mm Type X gypsum board

The loadbearing walls in the wood frame building consisted of staggered 2×6 in. on a 2×8 in. base plate. Following W7 (a and b) from Table 9.10.3.1-B, with fiberglass insulation these walls would require 15.9 mm Type X gypsum board on both sides of the wall, if the insulation comes from fibre processed from rock or slag a 12.7 mm Type X gypsum board will suffice.

This is a complex system required to achieve a relatively low threshold for fire resistance. To achieve this rating, the wall cannot contain perforations without a fire seal, all gaps and seams must be properly sealed. The expectation is that it has been installed properly and, over the long term, residents do not alter or damage the gypsum board (as any damage would degrade the fire rating).

By contrast, in a loadbearing masonry building option, the 10 in. hollowcore floor planks provide a 2+ hr. fire rating for the floor system (topping layer of concrete and gypsum board ceilings could increase this). The loadbearing walls are constructed of 20 cm concrete masonry units and typical block has a fire rating of 1:49 hr. while use of light weight block (with aggregates conforming to building code requirements) or 60% solid normal weight units will achieve 2+ hr. fire ratings<sup>5</sup>. That is from the block alone, if walls are grouted solid a fire rating of 4+ hr. is achieved, if normal gypsum board is used to cover the block (often done in residential units anyways), a rating of 2+ hr. is achieved and if Type X gypsum board is added then a rating of 3+ hr. is achieved. It would be unlikely that a resident could damage a concrete block wall or hollowcore plank enough to alter its fire rating over the life of the building.

In summary, the building code provides a minimum level of safety, which both masonry and wood frame can meet. However, masonry walls are more durable, non-combustible, provide redundancy outside of code minimums and achieves all of this without added expensive detailing. Residents and owners can be assured that their lives and their property are safe.

#### **Superior Sound-Proofing**

Similar to the fire-resistance rating, sound-proofing requirements can be separated as code minimums typically met in wood frame construction through additional insulation materials and details versus masonry systems that, often without additional detailing, provide a more resilient system and a rating class above the code required minimums. Sound-proofing is often a selling point for multi-residential buildings and is key for maintaining long-term tenants. The typical measurement used for describing a materials ability to reduce the transmission of sound is the Sound Transmission Class (STC). The higher the STC rating, the more effective that material is at reducing sounds transmission. **Table 10** describes some typical STC ratings and their effectiveness in reducing the transmission of sound.

#### Table 10 STC Ratings and What they Mean<sup>6</sup>

Operable STC Rating	What can be Heard
STC - 40	Loud Speech quietly audible as a murmur
STC - 45	Loud speech heard but not audible
STC - 50	Loud sounds such as musical instruments or a stereo can be faintly heard
STC - 55	Minimal transmission of sound
STC - 60	Good sound-proofing and most sounds do not disturb

The STC rating for the structural floor assembly in the conventional wood framed building, using detail F25d from NBCC (which was explained above for fire-resistance ratings) is 45, this would be insufficient according to the National Building Code of Canada, which requires at least a STC rating of 50 to be used, and as a result additional detailing would be needed above that required for fire. As noted previously, the performance of this system would then be heavily dependent on the long-term durability and sustained performance of the materials over time. By contrast, a 10 in. hollowcore floor plank alone has a STC rating of 52 and when a 2 in. topping is included the STC rating increases to 56. The addition of gypsum board or other floor/ceiling details would only increase this.

Consider next, the unit demising walls constructed of wood frame. The conventional wood framed building specified here has walls built to detail W7 in the NBCC, and an STC rating of 45 and 47 depending on if 12.7 mm Type X gypsum or 15.9 mm Type X gypsum is used respectively. This would have to be increased, again, to meet a minimum of 50. Normal-weight 20 cm concrete masonry units have a STC rating of 50 when hollow and 56 if grouted solid. Placing an interior finish on one or both sides of a hollow block increases this to at least 57 and up to 73<sup>7</sup>. For instance, a wall with regular 12.7 mm gypsum board on both side (Detail B6e) has an STC rating of 57, increased to 60 with the 15.9 mm Type X gypsum board.

### **Additional Benefits**

Concrete block masonry offers other benefits to users and owners in the long-term. The fact that is has an inherent durability ensures long-term fire and sound resistance is maintained, it means maintenance costs, especially those arising from extreme weather, are substantially smaller over the life span of the building. Concrete masonry does not rot and does not provide a source of food for mould. In typical residential buildings one the most costly types of damage is due to water leaks from unit-to-unit. There are no threats to the loadbearing elements of a masonry structure due to water, but water is an enemy of wood, and water damage in a wood frame structure may actually pose a threat to the structural elements as well as the fire and sound resisting elements. The Concrete Masonry Units (CMU) that comprise a loadbearing masonry wall are produced locally on demand. The raw material for CMU production is readily available locally throughout Canada from multiple sources and is not susceptible to material shortages and accompanying price fluctuations commonly seen with other building materials. Overall, masonry provides many quantifiable and tangible benefits over wood frame construction that justify a minimal cost premium.

## **Masonry Friendly Design**

Loadbearing masonry construction utilizes walls built with Concrete Masonry Units (CMUs) that serve a dual function. The walls act as both as:

- 1. the loadbearing system, and
- 2. as the environmental separation (demising walls) between adjoining units and common elements.

Careful consideration during the design stage for a loadbearing masonry building is critical for an efficient design to take advantage of the material and will help reduce costs. This section will highlight some of the important considerations a designer should have, when planning their loadbearing masonry project.

### **Timing of Construction**

It is preferable to time the start of masonry construction while nightly low temperatures are still above 4°C. When delayed to the winter months, masonry and concrete have additional costs for heating and hoarding overnight to ensure curing occurs properly. This, however, can be mitigated when masonry is also used for exterior walls. Due to the speed of construction with masonry, floors can be completed, and hollowcore planks put in place rather quickly allowing the structure to enclose itself to facilitate heating. With the building enclosed, all the interior work can continue over the winter and the building veneer finished come springtime.

### **Continuity of Loadbearing Walls**

An important consideration in the design of a loadbearing masonry building is that walls need to be continuous all the way down to the foundation. This can create challenges for buildings that have underground parking and buildings that have commercial space at grade. These challenges can easily be overcome, however, by considering the following general details and layout options.

- 1. For buildings without underground parking, or where a transfer slab is used, essentially any walls in the structure can be loadbearing (demising walls, exterior walls, stairwell or elevator walls, etc.). Hollowcore plank spans and orientations would then be free to bear in the direction most convenient as all masonry walls would be part of the structure.
- 2. When an underground garage or open commercial space is used at the bottom of the structure and no transfer slab is present, enough loadbearing wall area must be able to extend all the way into the foundation. The challenge is that the architectural layout for commercial space and parking garages do not often have walls that line up with residential floor layouts. See the subsection **Wall Location and Orientation** provides design advice to mitigate this.

### **Spacing Between Walls**

The spacing between walls is dependent on the spanning capacity of the flooring system, in this case the precast hollowcore planks. The capacity of the planks is based on the amount of reinforcing, as well as the loading conditions but the following information can be used for typical maximum spans, although specific manufacturers and loading conditions may dictate different limits. The following span limits were provided by taking a typical residential floor load and using the span tables provided in the Stubbes Hollowcore Span Tables<sup>8</sup>:

- 8 in. thick hollowcore plank can typically span up to 28 ft.
- 10 in. thick hollowcore plank can typically span up to 38 ft.
- 12 in. thick hollowcore plank can typically span up to 48 ft.


For this study in order to remove the need for a concrete transfer slab, the loadbearing walls were placed as unit demising walls to also take advantage of the fire and sound resisting properties of the masonry. The unit layout for this study was to have demising walls spaced at 38 ft. This is a typical for condos and rental units in Atlantic Canada. In order to use the 8 in. hollowcore planks for such a span, an intermediary loadbearing wall would be required. To avoid this a 10 in. plank was selected.

### Wall Location and Orientation

It is preferable to utilize loadbearing walls as demising walls between adjoining units and between units and common hallways as well as in exterior walls. This assures that the building will have walls orientated and possess strength when loaded by wind or earthquake forces along both axes (something that will greatly help with design). In the building used in this study only demising walls between units utilized loadbearing walls, which creates challenges from a masonry design perspective. Additional cost savings would be expected had the building layout been more masonry friendly as indicated in **Figure 3a**) and described below:

- 1. Including stairwells and elevator shaft walls as loadbearing elements that continue over the full building height and oriented perpendicular to the unit demising walls.
- 2. Aligning unit demising walls with walls separating parking spaces or zones.
- 3. Aligning unit walls with mechanical, locker or bicycle storage rooms in the parking garage to create continuity in layout.
- 4. Utilizing window and door placement to assure that enough strong walls are created along the exterior to resist loads.

As indicated in **Figure 3a**), when no transfer slab is used and underground parking is required, it is relatively easy for designers to utilize the indicated loadbearing masonry walls (dark lines) in a parking garage based on the residential floor layouts. Walls used in upper floors that do not carry to the foundation (light lines) as loadbearing elements are not participating in the structural design, although they still serve an architectural function and act to provide fire and sound resistance. Indicated in **Figure 3b**) is the scenario when a transfer slab is used or the structure does not contain underground parking, all walls can be utilized as loadbearing elements over their height. In both cases walls are sufficiently orientated along both axes.



a) Underground Parking

b) Transfer Slab or No Underground Parking

Figure 3 Comparing loadbearing masonry wall layout for buildings with and without underground parking

## **Comparison to a Previous Study**

The results of this current study can be used in conjunction with the results published by Walter G.M Schneider III titled "*Initial Cost of Construction: Multi-Residential Structures*<sup>9</sup>". Which was published in 2017 and included 23 American cities and 8 Canadian cities. This current study is compared to the published results reported for Halifax, NS in **Table 11**.

Building System	Relative Cost for Current Study (with Underground Parking)	Relative Cost for Previous Study <sup>9</sup>
Conventional Wood Framing	100	100
Loadbearing Masonry	104	105

Table 11 Results Comparison to "Initial Cost of Construction: Multi-Residential Structures"

The results from the two studies actually end up remarkably similar and both and show that a loadbearing masonry building is within 5% of the building cost for conventional wood framing. The differences between the studies are reported next.

#### **Construction Location**

The first main difference between the two studies is the location. The previous study looked at the cost of construction for Halifax, NS while the current study looked at the cost of construction for Moncton, NB. These locations are only 150 km from each other, but from a design perspective it can be quite different. Halifax is known to have strong soil conditions, this allows for a reduced seismic load in the structural design. Changes in the seismic load will have minimal difference for a low weight construction like conventional wood framing, but will be cause for a significant increase in seismic loading for heavier construction materials like loadbearing masonry and concrete. The other main difference between the two locations is the building codes. As of the time in writing this study, New Brunswick is operating under the 2010 Building Code, and Nova Scotia has adopted the 2015 Building Code. However, for the *Initial Cost of Construction* study, the buildings were designed to the 2005 International Building Code.

### **Scope of Study**

Another difference between the studies is their scope. The previous study provided a full estimate of the hard costs for a finished building including interior finishes, HVAC, and building veneer. Whereas, the current study looked at the costs associated with the **structure and building enclosure only**. To establish a total building cost, a conservative estimate was made based on a fixed ratio of structure costs to total building costs. The scope of this study was limited in order to provide **a base cost of construction**, the choices for finishes and building veneer could then be up to the design team.

### **Building Layout**

The conceptual building selected for each study were also fundamentally different. The previous study was conducted in 25 cities across North America and utilized the same 3-storey structure throughout (versus 4-storey building used in the current study). As a result, a building layout was selected that would not necessarily be expected in Atlantic Canada. The current study is based on a unit size that necessitated the use of a 10 in. hollowcore floor plank, whereas the previous study utilized 8 in. planks.

## Conclusion

The cost estimates prepared by Acadian Construction shows that loadbearing masonry is a viable building material in the mid-rise multi-residential market for Atlantic Canada, and this study further strengthens the results published in the previous *Initial Cost of Construction: Multi-Residential Structure* study.

The primary objective of this study focused on the detailed cost estimates and construction timelines for the building structure and the exterior enclosure (studs and sheathing only) of the 4-storey model building in Atlantic Canada. Major takeaways from this study include;

- The loadbearing masonry structures are substantially quicker to construct than conventional wood framing and cast in-place concrete structures. Loadbearing masonry was 14 weeks faster to build when a parking garage was included and 10 weeks faster to build without a parking garage compared to conventional wood framing. In addition, loadbearing masonry was 18 weeks faster to build when a parking garage was included and 16 weeks faster to build without a parking garage compared to cast in-place concrete.
- 2. In comparison with conventional wood framing, the loadbearing masonry structure was 11% higher in cost when a parking garage was included and 24% higher in cost without a parking garage.
- 3. In comparison with cast in-place concrete, the loadbearing masonry structure was 28% cheaper in cost when a parking garage was included and 26% cheaper in cost without a parking garage.

Further to the primary objective of investigating the construction cost construction timelines for the building structure and exterior enclosure, this study also demonstrated that even with conservative estimates of total building construction costs and utilizing a building layout that is not particularly masonry friendly, loadbearing masonry was within 4% and 8% of the costs for wood frame buildings with and without a parking garage, respectively. This outcome is consistent with previously published material *"Initial Cost of Construction: Multi-Residential Structures<sup>9</sup>"*.

Finally, this study highlights some of the many benefits associated with masonry construction when compared to typical wood frame construction. This includes added durability and resilience for using non-combustible materials with added redundancy when subject to fire or moisture issues. It was demonstrated that although all structures meet code minimums, masonry typically exceeds these limits, and some cases, offers many times more fire resistance or noise mitigation than expected from even specially detailed wood frame construction.

In conclusion, for what would amount to as a nominal hard cost price differential between masonry and wood frame a developer would reap numerous tangible and intangible benefits. While loadbearing masonry is not a one-size-fits-all solution to all residential buildings, in this study it was demonstrated to be a viable and competitive option for Atlantic Canada.

### References

1. Canada Mortgage and Housing Corporation "Rental Market Report – Halifax CMA", January 2020.

(https://assets.cmhc-schl.gc.ca/sites/cmhc/data-research/publications-reports/rentalmarket-reports/2019/rental-market-reports-halifax-64387-2020-a01-en.pdf?rev=2797a15ce25b-48a6-b4d1-a26964484bbd)

- Canada Mortgage and Housing Corporation "Rental Market Report Data Tables", 2019 Rental Market Survey, Oct. 2019. (<u>https://www.cmhc-schl.gc.ca/en/data-and-research/data-tables/rental-market-report-data-tables</u>)
- "Concrete Masonry Fire Resistance" Video (<u>https://www.youtube.com/watch?v=eaSUtFsvCDg</u>), National Concrete Masonry Association (NCMA), Herndon, VA.
- 4. Department of Health and Human Services "Preventing Deaths and Injuries of Fire Fighters Working Above Fire-Damaged Floors" Centers for Disease Control and National Institute for Occupational Safety and Health, DHHS (NIOSH) Publication No. 2009–114, Feb. 2009. (<u>https://www.cdc.gov/niosh/docs/wp-solutions/2009-114/pdfs/2009-114.pdf?id=10.26616/NIOSHPUB2009114</u>)
- 5. Canadian Concrete Masonry Producers Association (CCMPA), "Fire Performance", Metric Technical Manual, 2012. (<u>https://ccmpa.ca/wp-content/uploads/2012/02/Final2013-Sec5.pdf</u>)
- 6. https://en.wikipedia.org/wiki/Sound\_transmission\_class
- Canadian Concrete Masonry Producers Association (CCMPA), "Sound Properties and Design Details", Metric Technical Manual, 2012. <u>https://ccmpa.ca/wp-content/uploads/2012/02/7-SndProp.pdf</u>
- 8. Stubbe's Precast, "Hollowcore Floor Slabs Span and Connection Details". https://www.stubbes.org/file\_uploads/Hollow\_Core.pdf
- 9. Walter G. M. Schneider III, "Initial Cost of Construction: Multi-Residential Structures" Canadian Concrete Masonry Producers Association (<u>https://ccmpa.ca/resources-publications/cost-analysis-studies/</u>)


### **Contact Info**

#### Canada Masonry Design Centre:

360 Superior Blvd. Mississauga, Ontario L5T 2N7 Phone: 1-888-338-3336 E-Mail: <u>cmdc@canadamasonrycentre.com</u> Atlantic Masonry Institute: 99 Wyse Road, #1117, Dartmouth, NS B3A 4S5 Phone: 902-418-5065 E-Mail: info@atlanticmasonryinstitute.com

Canadian Concrete Masonry Producers Association: PO Box # 1492 Waterdown, Ontario LOR 2H0 Phone: 365-323-5024 Email: <u>A.mcchesney@ccmpa.ca</u>

## **APPENDIX A – Floor Layout**



## **APPENDIX B – Construction Schedule**

Dit         Dit <thdit< th=""> <thdit< th=""> <thdit< th=""></thdit<></thdit<></thdit<>	Mode         Image: Non 20-05 Wed 21:01:13         05:00         05:10         05:14         06:28         07:12         07:26         08:09         06:23         09:06         09:20         10:04         11:10         11:15         11:29         12:32         01:07           Mobilize         3 days         Mon 20:05 OWed 20:05:01         Construction         Foundation         60:62         09:20         10:04         10:18         11:10         11:15         11:29         12:32         01:16           Mobilize         3 days         Mon 20:05 OWed 20:05:01         Foundation         60:52         Foundation         60:52         Foundation         60:23         00:62         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71         00:71	- 1		Task Name	Duration	Start	Finish				Mav			July	v			0	ptember				November				Janua	rv	
Construction       176 days       Mon 20-95-0Wed 21:01:13       Construction       Construction       Of ::T         Mobilize       3 days       Mon 20-95-0Wed 20:05:06       Mobilize       05:21       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       07:15       06:23       06:23       07:15       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23	Construction       176 days       Mon 20-95-0Wed 21:01:13       Construction       Construction       Of ::T         Mobilize       3 days       Mon 20-95-0Wed 20:05:06       Mobilize       05:21       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       07:15       06:23       06:23       07:15       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23       06:23							03-22	04-05	04-19	05-03	05-17	05-31		28 07-12	07-26	08-09	08-23	09-06	09-20	10-04			11-15	11-29	12-13	12-27	01-10	-
Mobilize       3 days       Mon 20-05-0Wed 20-05-06       Mobilize       05-06         foundation       64/20       10 days       Thu 20-05-271 thu 20-05-21       65-06         foundation       64/20       64/20       65-21       06-23         slab prep       3 wks       Wed 20-06-2/Wed 20-07-12       65-21       06-23         place slabs SOG       1 wk       Thu 20-07-2/Wed 20-07-22       place slabs SOG 0.1 wk       Thu 20-07-2/Wed 20-07-22         Frame walls level 1       21 days       Thu 20-07-2/Wed 20-07-22       place slabs SOG 0.1 wk       Thu 20-07-2/Wed 20-07-22         frame floor level 2       11 days       Thu 20-07-2/Wed 20-07-22       Place slabs SOG 0.1 wk       10 days         frame floor level 2       11 days       Tu 20-07-2/Wed 20-07-22       Place slabs SOG 0.1 wk       10 days         frame floor level 3       10 days       Wed 20-10-1/We 20-10-27       Place slabs SOG 0.1 wk       10 days         frame floor level 3       10 days       Wed 20-10-1/We 20-10-27       Place slabs slab reping walls level 3       10 -27         frame floor level 4       10 days       Fri 20-12-1/W 20-10-27       Frame walls level 3       10 -27         frame floor level 4       10 days       Fri 20-12-1/W 20-10-27       Frame Roof       6 days       Mon 20-10-17 <td>Mobilize       3 days       Mon 20-05-0Wed 20-05-06       Mobilize       05-06         foundation       64/20       10 days       Thu 20-05-271 thu 20-05-21       65-06         foundation       64/20       64/20       65-21       06-23         slab prep       3 wks       Wed 20-06-2/Wed 20-07-12       65-21       06-23         place slabs SOG       1 wk       Thu 20-07-2/Wed 20-07-22       place slabs SOG 0.1 wk       Thu 20-07-2/Wed 20-07-22         Frame walls level 1       21 days       Thu 20-07-2/Wed 20-07-22       place slabs SOG 0.1 wk       Thu 20-07-2/Wed 20-07-22         frame floor level 2       11 days       Thu 20-07-2/Wed 20-07-22       Place slabs SOG 0.1 wk       10 days         frame floor level 2       11 days       Tu 20-07-2/Wed 20-07-22       Place slabs SOG 0.1 wk       10 days         frame floor level 3       10 days       Wed 20-10-1/We 20-10-27       Place slabs SOG 0.1 wk       10 days         frame floor level 3       10 days       Wed 20-10-1/We 20-10-27       Place slabs slab reping walls level 3       10 -27         frame floor level 4       10 days       Fri 20-12-1/W 20-10-27       Frame walls level 3       10 -27         frame floor level 4       10 days       Fri 20-12-1/W 20-10-27       Frame Roof       6 days       Mon 20-10-17<td></td><td></td><td>Construction</td><td>176 days</td><td>Mon 20-05-0</td><td>Wed 21-01-13</td><td></td><td>Con</td><td>struction</td><td></td><td></td><td></td><td></td><td></td><td></td><td><u></u></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>+</td><td>01-</td><td>- 13</td></td>	Mobilize       3 days       Mon 20-05-0Wed 20-05-06       Mobilize       05-06         foundation       64/20       10 days       Thu 20-05-271 thu 20-05-21       65-06         foundation       64/20       64/20       65-21       06-23         slab prep       3 wks       Wed 20-06-2/Wed 20-07-12       65-21       06-23         place slabs SOG       1 wk       Thu 20-07-2/Wed 20-07-22       place slabs SOG 0.1 wk       Thu 20-07-2/Wed 20-07-22         Frame walls level 1       21 days       Thu 20-07-2/Wed 20-07-22       place slabs SOG 0.1 wk       Thu 20-07-2/Wed 20-07-22         frame floor level 2       11 days       Thu 20-07-2/Wed 20-07-22       Place slabs SOG 0.1 wk       10 days         frame floor level 2       11 days       Tu 20-07-2/Wed 20-07-22       Place slabs SOG 0.1 wk       10 days         frame floor level 3       10 days       Wed 20-10-1/We 20-10-27       Place slabs SOG 0.1 wk       10 days         frame floor level 3       10 days       Wed 20-10-1/We 20-10-27       Place slabs slab reping walls level 3       10 -27         frame floor level 4       10 days       Fri 20-12-1/W 20-10-27       Frame walls level 3       10 -27         frame floor level 4       10 days       Fri 20-12-1/W 20-10-27       Frame Roof       6 days       Mon 20-10-17 <td></td> <td></td> <td>Construction</td> <td>176 days</td> <td>Mon 20-05-0</td> <td>Wed 21-01-13</td> <td></td> <td>Con</td> <td>struction</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td><u></u></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>+</td> <td>01-</td> <td>- 13</td>			Construction	176 days	Mon 20-05-0	Wed 21-01-13		Con	struction							<u></u>										+	01-	- 13
foundation excavation       10 days       Thu 20-05-07 Thu 20-05-21       foundation excavation       05-21         foundation       6 wks       Tue 20-05-12 Tue 20-06-23       foundation       06-23         slab prep       3 wks       Wed 20-06-22 Wed 20-07-15       slab prep       07-15         place slabs SOG       1 wk       Thu 20-07-35 fri 20-08-21       place slabs SOG       07-22         Frame walls level 1       21 days       Thu 20-07-35 fri 20-08-21       place slabs SOG       07-22         frame floor level 2       10 days       Wed 20-00-214       Frame walls level 1       08-21       08-21         frame floor level 3       10 days       Wed 20-00-1142       Frame walls level 2       10 days       10 days       Wed 20-00-1142       10 days       10 days       10 days       10 days       10 days       10 days       Wed 20-00-1142       10 days       10 days       10 days       10 days       10 days       Wed 20-00-1142       10 days       10 days       10 days       10 days       10 days       Wed 20-00-1142       12-20       12-20       12-20       12-20       12-20       12-20       12-20       12-20       12-20       12-20       12-20       12-20       12-20       12-20       12-20       12-20       12-20       1	foundation excavation       10 days       Thu 20-05-07 Thu 20-05-21       foundation excavation       05-21         foundation       6 wks       Tue 20-05-12 Tue 20-06-23       foundation       06-23         slab prep       3 wks       Wed 20-06-22 Wed 20-07-15       slab prep       07-15         place slabs SOG       1 wk       Thu 20-07-35 fri 20-08-21       place slabs SOG       07-22         Frame walls level 1       21 days       Thu 20-07-35 fri 20-08-21       place slabs SOG       07-22         frame floor level 2       10 days       Wed 20-00-214       Frame walls level 1       08-21       08-21         frame floor level 3       10 days       Wed 20-00-1142       Frame walls level 2       10 days       10 days       Wed 20-00-1142       10 days       10 days       10 days       10 days       10 days       10 days       Wed 20-00-1142       10 days       10 days       10 days       10 days       10 days       Wed 20-00-1142       10 days       10 days       10 days       10 days       10 days       Wed 20-00-1142       12-20       12-20       12-20       12-20       12-20       12-20       12-20       12-20       12-20       12-20       12-20       12-20       12-20       12-20       12-20       12-20       12-20       1											6 1		- <u> </u>		·				r — I		- <u> </u>				<u> </u>	т —		Ť
foundation       6 wks       Tue 20-05-12 Tue 20-06-23       foundation       0F-23         slab prep       3 wks       Wed 20-06-22 Wed 20-07-15       slab prep       07-15         place slabs SOG       1 wk       Thu 20-07-15 Wed 20-07-22       Frame walls level 1       21 days         frame floor level 2       11 days       Mu 20-07-23 Fri 20-08-21       Frame walls level 1       08-21         frame floor level 2       11 days       Wed 20-07-23 Fri 20-08-21       Frame walls level 1       09-14       09-14         frame floor level 2       11 days       Wed 20-01-17 We 20-01-13       Frame walls level 2       09-14       09-14         frame floor level 3       10 days       Wed 20-10-21 Thu 20-11-26       Frame walls level 3       10 days       Frame walls level 4       10 days       Fri 20-11-27         frame Roof       Frame Roof       6 days       Mor 20-12-21 Thu 20-12-26       Frame Roof       Frame walls level 4       10 days       Fri 20-11-27       12-10         frame Roof       6 days       Mor 20-12-21 Thu 20-12-26       Frame Roof       Frame Roof       Frame Roof       12-10       12-10         frame Roof       6 days       Mor 20-12-21 Thu 20-12-26       Frame Roof       Frame Roof       Sab topping Ivl 4       12-10       12-10       12-10	foundation       6 wks       Tue 20-05-12 Tue 20-06-23       foundation       0F-23         slab prep       3 wks       Wed 20-06-22 Wed 20-07-15       slab prep       07-15         place slabs SOG       1 wk       Thu 20-07-15 Wed 20-07-22       Frame walls level 1       21 days         frame floor level 2       11 days       Mu 20-07-23 Fri 20-08-21       Frame walls level 1       08-21         frame floor level 2       11 days       Wed 20-07-23 Fri 20-08-21       Frame walls level 1       09-14       09-14         frame floor level 2       11 days       Wed 20-01-17 We 20-01-13       Frame walls level 2       09-14       09-14         frame floor level 3       10 days       Wed 20-10-21 Thu 20-11-26       Frame walls level 3       10 days       Frame walls level 4       10 days       Fri 20-11-27         frame Roof       Frame Roof       6 days       Mor 20-12-21 Thu 20-12-26       Frame Roof       Frame walls level 4       10 days       Fri 20-11-27       12-10         frame Roof       6 days       Mor 20-12-21 Thu 20-12-26       Frame Roof       Frame Roof       Frame Roof       12-10       12-10         frame Roof       6 days       Mor 20-12-21 Thu 20-12-26       Frame Roof       Frame Roof       Sab topping Ivl 4       12-10       12-10       12-10							fou	Indation				1 +		+		+		+		-+					<u> </u> – –	+		
slab prep       3 wks       Wed 20-06-2/Wed 20-07-15       slab prep       07-15         place slabs SOG       1 wk       Thu 20-07-16/Wed 20-07-12       place slabs SOG       07-22         Frame walls level 1       21 days       Thu 20-07-28/12 0.08-21       Frame walls level 1       08-21         frame floor level 2       15 days       Mon 20-08-21/Mon 20-09-14       Frame walls level 1       08-21         frame floor level 3       10 days       Wed 20-10-17/Wed 20-07-22       Frame walls level 2       10-27         frame floor level 3       10 days       Wed 20-10-17/Wed 20-10-27       Frame walls level 3       10-27         frame floor level 3       10 days       Wed 20-10-17/Wed 20-10-27       Frame walls level 3       10-27         frame floor level 4       10 days       Fri 20-11-27 Thu 20-12-24       Frame walls level 3       10-27         frame floor level 4       10 days       Fri 20-12-27 Thu 20-12-24       Frame walls level 3       12-26         frame floor level 4       10 days       Fri 20-12-7 Thu 20-12-24       Frame walls level 4       10-27         frame floor level 4       10 days       Fri 20-12-7 Thu 20-12-24       Frame walls level 4       10-20         frame floor level 4       10 days       Fri 20-12-7 Thu 20-12-24       Frame walls level 4       12-24<	slab prep       3 wks       Wed 20-06-2/Wed 20-07-15       slab prep       07-15         place slabs SOG       1 wk       Thu 20-07-16/Wed 20-07-12       place slabs SOG       07-22         Frame walls level 1       21 days       Thu 20-07-28/12 0.08-21       Frame walls level 1       08-21         frame floor level 2       15 days       Mon 20-08-21/Mon 20-09-14       Frame walls level 1       08-21         frame floor level 3       10 days       Wed 20-10-17/Wed 20-07-22       Frame walls level 2       10-27         frame floor level 3       10 days       Wed 20-10-17/Wed 20-10-27       Frame walls level 3       10-27         frame floor level 3       10 days       Wed 20-10-17/Wed 20-10-27       Frame walls level 3       10-27         frame floor level 4       10 days       Fri 20-11-27 Thu 20-12-24       Frame walls level 3       10-27         frame floor level 4       10 days       Fri 20-12-27 Thu 20-12-24       Frame walls level 3       12-26         frame floor level 4       10 days       Fri 20-12-7 Thu 20-12-24       Frame walls level 4       10-27         frame floor level 4       10 days       Fri 20-12-7 Thu 20-12-24       Frame walls level 4       10-20         frame floor level 4       10 days       Fri 20-12-7 Thu 20-12-24       Frame walls level 4       12-24<											· — ·		06-23		·		·		- — I						<u> </u>	T —		
place slabs SOG       1 wk       Thu 20-07-16 Wed 20-07-22       place slabs SOG       07-22       08-21         Frame walls level 1       21 days       Thu 20-07-23 fri 20-08-21       Frame walls level 1       08-21       10-13         Frame floor level 2       10 days       Walls level 1       10-13       10-13         Frame walls level 2       10 days       Wed 20-10-17 tru 20-10-27       Frame walls level 3       10 days       Wed 20-10-17 tru 20-10-27         Frame walls level 3       10 days       Wed 20-10-17 tru 20-10-27       Frame walls level 4       10-27       Frame walls level 3       11-26         Frame walls level 4       10 days       Fri 20-12.71 thu 20-12.40       Frame walls level 4       <	place slabs SOG       1 wk       Thu 20-07-16 Wed 20-07-22       place slabs SOG       07-22       08-21         Frame walls level 1       21 days       Thu 20-07-23 fri 20-08-21       Frame walls level 1       08-21       10-13         Frame floor level 2       10 days       Walls level 1       10-13       10-13         Frame walls level 2       10 days       Wed 20-10-17 tru 20-10-27       Frame walls level 3       10 days       Wed 20-10-17 tru 20-10-27         Frame walls level 3       10 days       Wed 20-10-17 tru 20-10-27       Frame walls level 4       10-27       Frame walls level 3       11-26         Frame walls level 4       10 days       Fri 20-12.71 thu 20-12.40       Frame walls level 4       <								+	-	┢ ′ᄏ		slab	prep		5	+	+ •	+-		-+		- +				+		+
Frame walls level 1       21 days       Thu 20-07-23 Fri 20-08-21       Frame walls level 1       08-21       08-21         Frame floor level 2       15 days       Mon 20-08-2/Mon 20-09-14       Frame walls level 2       10-13         Frame walls level 2       21 days       Wed 20-10-15 Tue 20-10-13       Frame walls level 2       10-13         Frame walls level 3       10 days       Wed 20-10-27h u20-12-7h       Frame walls level 3       10-27         Frame walls level 4       10 days       Fri 20-12-7h u20-12-7h       Frame walls level 3       10-27         Frame walls level 4       10 days       Fri 20-12-7h u20-12-7h       Frame walls level 4       12-10         Frame walls level 4       10 days       Fri 20-12-7h u20-12-7h       Frame walls level 4       12-24         Frame walls level 4       10 days       Fri 20-12-7h u20-12-7h       Frame walls level 4       12-24         Frame Roof       6 days       Mon 20-12-2iTue 21-01-05       Frame Roof       10-10-7h       101-07         Salab topping Ivl 4       2 days       Fri 20-10-17h u20-10-7h       Frame Roof       6 days       Mon 20-08-27h u20-0h       10-107         Salab topping Ivl 3       2 days       Fri 20-10-07h u21-01-07h       Int 17h u20-12-2h       Int 17h u20-12-2h       Int 17h u20-12-2h       Int 17h u20-12-2h <td>Frame walls level 1       21 days       Thu 20-07-23 Fri 20-08-21       Frame walls level 1       08-21       08-21         Frame floor level 2       15 days       Mon 20-08-2/Mon 20-09-14       Frame walls level 2       10-13         Frame walls level 2       21 days       Wed 20-10-15 Tue 20-10-13       Frame walls level 2       10-13         Frame walls level 3       10 days       Wed 20-10-27h u20-12-7h       Frame walls level 3       10-27         Frame walls level 4       10 days       Fri 20-12-7h u20-12-7h       Frame walls level 3       10-27         Frame walls level 4       10 days       Fri 20-12-7h u20-12-7h       Frame walls level 4       12-10         Frame walls level 4       10 days       Fri 20-12-7h u20-12-7h       Frame walls level 4       12-24         Frame walls level 4       10 days       Fri 20-12-7h u20-12-7h       Frame walls level 4       12-24         Frame Roof       6 days       Mon 20-12-2iTue 21-01-05       Frame Roof       10-10-7h       101-07         Salab topping Ivl 4       2 days       Fri 20-10-17h u20-10-7h       Frame Roof       6 days       Mon 20-08-27h u20-0h       10-107         Salab topping Ivl 3       2 days       Fri 20-10-07h u21-01-07h       Int 17h u20-12-2h       Int 17h u20-12-2h       Int 17h u20-12-2h       Int 17h u20-12-2h<td></td><td></td><td></td><td></td><td></td><td></td><td></td><td><u> </u></td><td></td><td><u> </u></td><td>i — T</td><td><u> </u></td><td>place slabs</td><td>s SOG</td><td>07-22</td><td>-<u> </u></td><td></td><td></td><td>- — I</td><td></td><td></td><td>— —</td><td></td><td></td><td></td><td>ī —</td><td></td><td>1</td></td>	Frame walls level 1       21 days       Thu 20-07-23 Fri 20-08-21       Frame walls level 1       08-21       08-21         Frame floor level 2       15 days       Mon 20-08-2/Mon 20-09-14       Frame walls level 2       10-13         Frame walls level 2       21 days       Wed 20-10-15 Tue 20-10-13       Frame walls level 2       10-13         Frame walls level 3       10 days       Wed 20-10-27h u20-12-7h       Frame walls level 3       10-27         Frame walls level 4       10 days       Fri 20-12-7h u20-12-7h       Frame walls level 3       10-27         Frame walls level 4       10 days       Fri 20-12-7h u20-12-7h       Frame walls level 4       12-10         Frame walls level 4       10 days       Fri 20-12-7h u20-12-7h       Frame walls level 4       12-24         Frame walls level 4       10 days       Fri 20-12-7h u20-12-7h       Frame walls level 4       12-24         Frame Roof       6 days       Mon 20-12-2iTue 21-01-05       Frame Roof       10-10-7h       101-07         Salab topping Ivl 4       2 days       Fri 20-10-17h u20-10-7h       Frame Roof       6 days       Mon 20-08-27h u20-0h       10-107         Salab topping Ivl 3       2 days       Fri 20-10-07h u21-01-07h       Int 17h u20-12-2h       Int 17h u20-12-2h       Int 17h u20-12-2h       Int 17h u20-12-2h <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td><u> </u></td> <td></td> <td><u> </u></td> <td>i — T</td> <td><u> </u></td> <td>place slabs</td> <td>s SOG</td> <td>07-22</td> <td>-<u> </u></td> <td></td> <td></td> <td>- — I</td> <td></td> <td></td> <td>— —</td> <td></td> <td></td> <td></td> <td>ī —</td> <td></td> <td>1</td>								<u> </u>		<u> </u>	i — T	<u> </u>	place slabs	s SOG	07-22	- <u> </u>			- — I			— —				ī —		1
frame floor level 2       15 days       Mon 20-08-2: Mon 20-09-14       Image: frame floor level 2       10-13         Frame walls level 2       21 days       Tue 20-09-15 Tue 20-10-13       Image: frame floor level 3       10-13       Image: frame floor level 3       10-27       Image: frame floor level 3       10-13       Image: frame floor level 4       10-27       Image: frame floor level 4       10-27       Image: frame floor level 4       10 days       10 days       10 days       10 days       Frame floor level 4	frame floor level 2       15 days       Mon 20-08-2: Mon 20-09-14       Image: frame floor level 2       10-13         Frame walls level 2       21 days       Tue 20-09-15 Tue 20-10-13       Image: frame floor level 3       10-13       Image: frame floor level 3       10-27       Image: frame floor level 3       10-13       Image: frame floor level 4       10-27       Image: frame floor level 4       10-27       Image: frame floor level 4       10 days       10 days       10 days       10 days       Frame floor level 4									-	-		$\vdash$ $\dashv$	Frame wa	alls level 1	- I	+	08-21	+		-+						+		+
Frame walls level 2       21 days       Tue 20-09-15 Tue 20-10-13       Image: constraint of the c	Frame walls level 2       21 days       Tue 20-09-15 Tue 20-10-13       Image: constraint of the c									- <u> </u>		i — ī				frame fl	oor level	2	09	-14		- <u> </u>					ī —		ï
if ame floor level 3       10 days       Wed 20-10-1/Tue 20-10-27         if ame floor level 3       21 days       Wed 20-10-2/Thu 20-12-60         if ame floor level 4       10 days       Fri 20-11-27         if ame floor level 4       10 days       Fri 20-12-7         if ame floor level 4       10 days       Fri 20-12-7         if ame floor level 4       10 days       Fri 20-12-7         if ame floor level 4       10 days       Fri 20-12-10         if ame floor level 4       10 days       Fri 20-12-27         if ame floor level 4       10 days       Fri 20-12-10         if ame floor level 4       10 days       Fri 20-12-27         if ame floor level 4       10 days       Fri 20-12-27         if ame floor level 4       10 days       Fri 20-10-05         if ame floor level 4       2 days       Wed 21-01-01/10-07         is alb topping lvl 4       2 days       Wed 21-01-01/10-07         is alb topping lvl 2       2 days       True 21-01-12         is alb topping lvl 2       2 days       True 21-01-12         is alb topping lvl 2       2 days       True 21-01-12         is alb topping lvl 2       2 days       Med 20-00-27         is alb topping lvl 2       2 days       Med 20-01-07-10-20-	if ame floor level 3       10 days       Wed 20-10-1/Tue 20-10-27         if ame floor level 3       21 days       Wed 20-10-2/Thu 20-12-60         if ame floor level 4       10 days       Fri 20-11-27         if ame floor level 4       10 days       Fri 20-12-7         if ame floor level 4       10 days       Fri 20-12-7         if ame floor level 4       10 days       Fri 20-12-7         if ame floor level 4       10 days       Fri 20-12-10         if ame floor level 4       10 days       Fri 20-12-27         if ame floor level 4       10 days       Fri 20-12-10         if ame floor level 4       10 days       Fri 20-12-27         if ame floor level 4       10 days       Fri 20-12-27         if ame floor level 4       10 days       Fri 20-10-05         if ame floor level 4       2 days       Wed 21-01-01/10-07         is alb topping lvl 4       2 days       Wed 21-01-01/10-07         is alb topping lvl 2       2 days       True 21-01-12         is alb topping lvl 2       2 days       True 21-01-12         is alb topping lvl 2       2 days       True 21-01-12         is alb topping lvl 2       2 days       Med 20-00-27         is alb topping lvl 2       2 days       Med 20-01-07-10-20-			Frame walls level 2		Tue 20-09-1	Tue 20-10-13		$\vdash$ $-$	-			-+			-	Fra	me walls le	evel 2 🎽		10	0-13					<u>+                                    </u>	<u> </u>	
Frame walls level 3       21 days       Wed 20-10-2i Thu 20-11-26       Frame walls level 4       10 days       Fri 20-11-27       Thu 20-11-26       Frame walls level 4       11-26         Frame more foor level 4       10 days       Fri 20-11-27       Thu 20-12-24       Fri 20-12-10       Frame walls level 4       12-10         Frame walls level 4       10 days       Fri 20-12-10       Fri 20-12-10       Fri 20-12-10       Frame walls level 4       12-24         Frame walls level 4       10 days       Fri 20-12-10-05       Frame walls level 4       12-24       01-05         slab topping M 4       2 days       Wed 21-00-10Thu 21-01-07       Slab topping M 4       01-05         slab topping M 3       2 days       Fri 20-12-10       Slab topping M 4       01-07         slab topping M 2       2 days       Fri 20-12-10       Slab topping M 4       01-07         slab topping M 2       2 days       Fri 20-10-10       Slab topping M 2       01-01         slab topping M 2       2 days       Fri 20-10-10       Slab topping M 2       01-01         slab topping M 2       2 days       More 20-00-27       Slab topping M 2       01-01         slab topping M 2       5 days       Wed 20-00-17-10-20-03       A/V Barrier & Roxul Ivi 1       08-27       01-02	Frame walls level 3       21 days       Wed 20-10-2i Thu 20-11-26       Frame walls level 4       10 days       Fri 20-11-27       Thu 20-11-26       Frame walls level 4       11-26         Frame more foor level 4       10 days       Fri 20-11-27       Thu 20-12-24       Fri 20-12-10       Frame walls level 4       12-10         Frame walls level 4       10 days       Fri 20-12-10       Fri 20-12-10       Fri 20-12-10       Frame walls level 4       12-24         Frame walls level 4       10 days       Fri 20-12-10-05       Frame walls level 4       12-24       01-05         slab topping M 4       2 days       Wed 21-00-10Thu 21-01-07       Slab topping M 4       01-05         slab topping M 3       2 days       Fri 20-12-10       Slab topping M 4       01-07         slab topping M 2       2 days       Fri 20-12-10       Slab topping M 4       01-07         slab topping M 2       2 days       Fri 20-10-10       Slab topping M 2       01-01         slab topping M 2       2 days       Fri 20-10-10       Slab topping M 2       01-01         slab topping M 2       2 days       More 20-00-27       Slab topping M 2       01-01         slab topping M 2       5 days       Wed 20-00-17-10-20-03       A/V Barrier & Roxul Ivi 1       08-27       01-02								1	- i						1	1		fram				0-27				<u> </u>		Ť
frame floor level 4       10 days       Fri 20-11-27       Thu 20-12-10       Frame walls level 4       10 days       Fri 20-11-21       Thu 20-12-10       Frame walls level 4       10 days       Fri 20-12-11       Thu 20-12-24       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1	frame floor level 4       10 days       Fri 20-11-27       Thu 20-12-10       Frame walls level 4       10 days       Fri 20-11-21       Thu 20-12-10       Frame walls level 4       10 days       Fri 20-12-11       Thu 20-12-24       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1			Frame walls level 3																Fram	e walls lev	vel 3 🎽			11-26				
Frame walls level 4       10 days       Fri 20-12-11 Thu 20-12-24       Image: Constraint of the c	Frame walls level 4       10 days       Fri 20-12-11 Thu 20-12-24       Image: Constraint of the c			frame floor level 4					<u> </u>					<u></u>		<u></u>			<u> </u>	· :		fran	ne floor	level 4 🏅		12-10	<u> </u>		ì
Frame Roof       6 days       Mon 20-12-2iTue 21-01-05       Frame Roof       01-05         slab topping M 4       2 days       Wed 21-01-0Tu - 12-10-07       slab topping M 4       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1	Frame Roof       6 days       Mon 20-12-2iTue 21-01-05       Frame Roof       01-05         slab topping M 4       2 days       Wed 21-01-0Tu - 12-10-07       slab topping M 4       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1       1			Frame walls level 4	10 days	Fri 20-12-11	Thu 20-12-24														- +		Fra	ne walls	level 4 🏅				
slab topping M3       2 days       Fri 21-01-08       Mon 21-01-11       slab topping M3       01-11         slab topping M2       2 days       Tue 21-01-12       Wed 21-01-13       slab topping M2       01-11         slab topping M2       2 days       Tue 21-01-12       Wed 21-01-13       slab topping M2       01-11         slab topping M2       4/V Barrier & Roxul M1       4 days       Mon 20-08-2/Th ue 20-08-2/Th       A/V Barrier & Roxul M1       08-27         A/V Barrier & Roxul M2       5 days       Wed 20-10-1/Tue 20-01-20       A/V Barrier & Roxul M1       08-27         A/V Barrier & Roxul M3       5 days       Fri 20-11-77       Thu 20-12-03       A/V Barrier & Roxul M1       02-20	slab topping M3       2 days       Fri 21-01-08       Mon 21-01-11       slab topping M3       01-11         slab topping M2       2 days       Tue 21-01-12       Wed 21-01-13       slab topping M2       01-11         slab topping M2       2 days       Tue 21-01-12       Wed 21-01-13       slab topping M2       01-11         slab topping M2       4/V Barrier & Roxul M1       4 days       Mon 20-08-2/Th ue 20-08-2/Th       A/V Barrier & Roxul M1       08-27         A/V Barrier & Roxul M2       5 days       Wed 20-10-1/Tue 20-01-20       A/V Barrier & Roxul M1       08-27         A/V Barrier & Roxul M3       5 days       Fri 20-11-77       Thu 20-12-03       A/V Barrier & Roxul M1       02-20			Frame Roof		Mon 20-12-2	Tue 21-01-05		·		<u> </u>			(	· <u> </u>	· · ·	<u> </u>		·	· :	<u> </u>	- <u> </u>	·	;					ì
slab topping lvl 3       2 days       Fri 21-01-08 Mon 21-01-11       slab topping lvl 3       01-11         slab topping lvl 2       2 days       Tue 21-01-12 Wed 21-01-13       slab topping lvl 3       01-11         slab topping lvl 3       V Barrier & Roxul lvl 1       08-27       slab topping lvl 2       01-13         slab topping lvl 3       Wed 20-00-12 Wed 20-00-20       VBarrier & Roxul lvl 1       08-27       08-27         slab topping lvl 3       Wed 20-10-17 Thu 20-10-02       VBarrier & Roxul lvl 2       02-04       10-20         slab topping lvl 3       Y Barrier & Roxul lvl 3       5 days       Wed 20-10-17 Thu 20-12-03       12-03	slab topping lvl 3       2 days       Fri 21-01-08 Mon 21-01-11       slab topping lvl 3       01-11         slab topping lvl 2       2 days       Tue 21-01-12 Wed 21-01-13       slab topping lvl 3       01-11         slab topping lvl 3       V Barrier & Roxul lvl 1       08-27       slab topping lvl 2       01-13         slab topping lvl 3       Wed 20-00-12 Wed 20-00-20       VBarrier & Roxul lvl 1       08-27       08-27         slab topping lvl 3       Wed 20-10-17 Thu 20-10-02       VBarrier & Roxul lvl 2       02-04       10-20         slab topping lvl 3       Y Barrier & Roxul lvl 3       5 days       Wed 20-10-17 Thu 20-12-03       12-03											1 †				1	+				- ++								
slab topping lvl 2       2 days       Tue 21-01-12 Wed 21-01-13       Image: Constraint of the con	slab topping lvl 2       2 days       Tue 21-01-12 Wed 21-01-13       Image: Constraint of the con		-						·	-:	·	· ·						·	·	~		'i		— — "	sl				
A/V Barrier & Roxul Ivl 1       4 days       Mon 20-08-2:Thu 20-08-27         A/V Barrier & Roxul Ivl 2       5 days       Wed 20-10-1:Tue 20-10-20         A/V Barrier & Roxul Ivl 3       5 days       Fri 20-11-27         Thu 20-12-03       Fri 20-11-27	A/V Barrier & Roxul Ivl 1       4 days       Mon 20-08-2:Thu 20-08-27         A/V Barrier & Roxul Ivl 2       5 days       Wed 20-10-1:Tue 20-10-20         A/V Barrier & Roxul Ivl 3       5 days       Fri 20-11-27         Thu 20-12-03       Fri 20-11-27								F —			†	-+			1	+				- ++					slab to	ping Ivi 2	2 101-1	13
A/V Barrier & Roxul Ivl 2       5 days       Wed 20-10-1. Tue 20-10-20       A/V Barrier & Roxul Ivl 2       10-20         A/V Barrier & Roxul Ivl 3       5 days       Fri 20-11-27       Thu 20-12-03       A/V Barrier & Roxul Ivl 3       12-03	A/V Barrier & Roxul Ivl 2       5 days       Wed 20-10-1. Tue 20-10-20       A/V Barrier & Roxul Ivl 2       10-20         A/V Barrier & Roxul Ivl 3       5 days       Fri 20-11-27       Thu 20-12-03       A/V Barrier & Roxul Ivl 3       12-03								·			· +			A/V Ba	rrier &	Roxul Ivi				- +	 	 				1		1
A/V Barrier & Roxul IvI 3 5 days Fri 20-11-27 Thu 20-12-03	A/V Barrier & Roxul IvI 3 5 days Fri 20-11-27 Thu 20-12-03								$\vdash$ —			1 †	-+				<b>—</b> –	A	A/V Barrie	r & Roxu							1		
A/V Barrier & Roxul Ivi 4 5 days Mon 20-12-2;Mon 21-01-04 0 -04	A/V Barrier & Roxul lvi 4 5 days Mon 20-12-2:Mon 21-01-04 A/V Barrier & Roxul lvi 4 🛀 0 -04			A/V Barrier & Roxul Ivl 3	5 days	Fri 20-11-27	Thu 20-12-03					· +				1			· · · · ·	I	A	VV Barrie	er & Rox	ul Ivi 3 🎽	12-0	3			
				A/V Barrier & Roxul IvI 4	5 days	Mon 20-12-2	Mon 21-01-04																	A/V Bar	rier & R	oxul Ivi 4	0	1-04	
ACL Schedule Wood no 20-01-31 Spit Summary Manual Task Deadline + Critical Spit Manual Progress												*				Ma	inual Progre	5											

ID 🔒	ACADIE	AN RUCTION ENNE				Pro	oject 1	9-131	LBM V	۷ood ۱	With P	arking	Garag	ge														
	Task Mode	Task Name	Duration	Start	Finish	03-22 04-05 04-19	May 05-03	05-17	05-31	06-14	July 06-28	07-12	07-26	08-09	08-23	September 09-06	09-20	10-04	10-18	Novemb 11-01	er 11-15	11-2	9   12-1	Jai 3   12-2	nuary 7 01-1	0 01-24	02-07	March
1 2		Construction	206 days	Mon 20-05-0	0 Thu 21-02-25	Construction	-	<u> </u>		+				-		+		—			+		-		<u>+</u> –			02-25
3		Mobilize	3 days		0-Wed 20-05-06	Mobilize		06	T —	Τ —	· · · · ·			η —				י – ו			Τ —	-ı						<u> </u>
4		foundation excavation	10 days		7 Thu 20-05-21	foundation excavati	on 📩	05	-21	+		$\vdash$ –		+	-	+ +		1-	+	+ -	+ -		+	+ -	+-	-	-+	
5	-	foundation	6 wks		2 Tue 20-06-23	founda	ation )			C	Q6-23			1				1			Τ —		1					
6		slab prep	3 wks		2-Wed 20-07-15	-+-+-	-	+	slab	prep 🎽		07-1		† —	-	+ -		1	-	+	+	-	+			-		
7	-	place slabs SOG	1 wk	Thu 20-07-1	6 Wed 20-07-22						slabs SO		<b>P7-22</b>	ï —				i —	1		T							
8	-	SOD level 1	5 wks		6 Thu 20-08-20	- + - + -			+ -	SC	OD level	4		+	08-20	+ -		1—		+ -	+ -	-1		+		-	- +	
9	-	Frame walls level 1	21 days	Fri 20-08-21	Mon 20-09-21					<u> </u>		Fram	e walls l		*		09-21		1		<u> </u>							
10	-,	frame floor level 2	15 days	Tue 20-09-2	2 Mon 20-10-12				$\top$ $-$					1	rame flo	or level 2			10-12	<u> </u>	+ -	_				-		
11	-,	Frame walls level 2	21 days	Tue 20-10-1	3 Tue 20-11-10		-	1	1	1	1			1	1	Frame	walls lev				11-10					_	h	
12		frame floor level 3	15 days	Thu 20-11-1	2 Wed 20-12-02				$\top$	T —						$\top \neg$		fran		level 3			-02	— –		-		
13		Frame walls level 3	21 days	Thu 20-12-0	3 Mon 21-01-04			1	1	1	1			1					1	Frame w	alls leve				01-04	_	h	
14		frame floor level 4	15 days	Tue 21-01-0	5 Mon 21-01-25													1				fran		level 4		01-25		
15	-,	Frame walls level 4	10 days		6 Mon 21-02-08							;		1		·			1		1			Frame w			02-08	
16	-,	Frame Roof	6 days	Tue 21-02-0	9 Wed 21-02-17									1		$\top$		1			Т					rame Roof		
17	-,	slab topping lvl 4	2 days	Thu 21-02-1	8 Fri 21-02-19		1				1			1	<u></u>			·	1		1	_;	1		s	ab topping		
18		slab topping lvl 3	2 days	Mon 21-02-2	2:Tue 21-02-23									1		$\top$		1			Т					slab toppi		
19	-,	slab topping lvl 2	2 days	Wed 21-02-2	2 Thu 21-02-25		1	$\square$						1											Lī .	slab topp	ing Ivl 2	02-25
20		A/V Barrier & Roxul IvI 1	4 days	Tue 20-09-2	2 Fri 20-09-25									A/V Ba	rrier & F	toxul Ivl 1	<b>0</b> 9-	25										
21		A/V Barrier & Roxul IvI 2	5 days		2 Wed 20-11-18					÷							A/V	Barrie	r & Rox	cul Ivi 2					Lī _			
22		A/V Barrier & Roxul Ivl 3	5 days	Tue 21-01-0	5 Mon 21-01-11																A/\	V Barrie	r & Rox	ul Ivi 3				
23		A/V Barrier & Roxul Ivl 4	5 days	Tue 21-02-0	9 Tue 21-02-16			1	i i	ì	i			i	i -	ii		i i	1	i i	i.	÷.	i.	Á/V Ba	arrier &	Roxul Ivi 4	02-	16
Project: A Date: Fri 2		le Wood w Task Split	Milestone Summary	¢ I	Manual Task Manual Sumi		Deadline	÷			ritical Split rogress				Manual Pro	gress												


1	Task T Mode	Fask Name	Duration	Start	Finish	04-05	04-19	lay	05-17	05-31	06-14	July 06-28	07-12	07-2		08-09	Sep 08-23	tember 09-06	09-	20	10-04	10-18	Novembe 11-0
						04-05	04-19	05-03	05-17	05-31	06-14	06-28	07-12	07-2		J8-09	08-23	09-06	09-	-20	10-04	10-18	
	<b>-</b> , C	Construction	126 days	Mon 20-05-04			Construction	· · · · · · · · · · · · · · · · · · ·															10-30
	-	Mobilize	3 days	Mon 20-05-04		<u> </u>	Mobilize											L	_				
	-,	foundation excavation	14 days	Thu 20-05-07		founda	ation excavat		0	05-27	<u> </u>	16-23	<u> </u>					÷ — –	<u> </u>				Ľ —
	-	foundation	6 wks	Tue 20-05-12			tour	dation		<u> </u>	slab prep	16-23	07-15					+					
	-	slab prep	3 wks	Wed 20-06-24			<u></u>		·	<u> </u>	siab prep	place slabs S		07-22				÷ — –	÷ —				
	÷	place slabs SOG Hollow core slabs lvl 1	1 wk 6 days	Thu 20-07-16 Thu 20-07-23			<u> </u>			+-	+	Hollow core			7-30			+					
_	-,	masonry lvl 1	7 days	Fri 20-07-31			<u></u>	·	·	<u>-</u>	<u> </u>		masonry			08-11		÷	÷ —				ť —
_		hollow core slabs lvl 2	6 days	Wed 20-08-12			<u> </u>			+	+-	+		v core sla			8-19	+	+	+			
	-,	masonry lvl 2	7 days	Thu 20-08-20			<u> </u>		·	<u>-</u>	<u> </u>	<u>+</u>	<u> </u>		masonry		08-2	<u>-</u>	÷ —				fi
!	-,	hollow core slabs lvl 3	6 days	Mon 20-08-31						+		+			hollow			09-08					
3	-	masonry lvl 3	7 days	Wed 20-09-09			<u> </u>	·	!	·	<u> </u>	<u> </u>	·	<u> </u>		-+	masonry lv	3	09-17				ť —
1	-,	hollow core slabs lvl 4	6 days	Fri 20-09-18	Fri 20-09-25											- +	hollow core	slabs Ivl 4	¥ -	09-25			
;	-,	masonry lvl 4	7 days	Mon 20-09-28	Tue 20-10-06		·	· · · · · · · · · · · · · · · · · · ·	·	<u> </u>	· ·		<u> </u>	<u> </u>					nry Ivl 4		10-06		ř —
5	-,	hollow core roof	7 days	Wed 20-10-07	Thu 20-10-15														hollow c	ore roof	· <b>* * * *</b> *	-15	
7	-	met stud framing lvl 1	3 days	Thu 20-08-20	Mon 20-08-24									met stud	d framing		08-24						[
	-,	met stud framing lvl 2	3 days	Wed 20-09-09												met stu		12 🍆 09-1					
)	-,	met stud framing IvI 3	3 days	Mon 20-09-28			<u> </u>	⊨		+	+	+	+	+			m	et stud fram					4
)	-	met stud framing lvl 4	3 days	Fri 20-10-16				ļ		$\perp$ $-$			$\perp$					$\perp \_ \_$			ning Ivl 4 🎽	10-20	
	-	slab topping lvl roof	2 days	Fri 20-10-16			<u> </u>	µ	ļ	+	+	+		+			⊢	+	slab		j Ivl roof 🎽		4
2	-	slab topping lvl 4	2 days	Wed 20-10-21			L	<u> </u> −	L	L	<u> </u>		L					∔			topping lvl 4		
	-	slab topping lvl 3	2 days	Fri 20-10-23			<u> </u>	⊨ — -	<u> </u>	+	+	+	+	+			⊢	+	+	sia	b topping lv slab toppin	3 10 10	10.20
1	-	slab topping lvl 2	2 days	Tue 20-10-27 Thu 20-10-29			<u> </u>	<b>├</b> ── -	┝── -	<u> </u>	→	+		+				+	+		slab toppin		
· · · · · · · · · · · · · · · · · · ·	-	slab topping lvl 1 A/V Barrier & Roxul lvl 1	2 days 6 days	Tue 20-08-25			<u> </u>	┢── -	<u> </u>	+	+	+	<u> </u>		arrier & R		0	9-01	+	++	sian robh		10-30
	->	A/V Barrier & Roxul Ivi 1 A/V Barrier & Roxul Ivi 2	7 days	Mon 20-09-14			<u> </u>	┝── -		+	+						arrier & Ro		- 09	-22		<u> </u>	
3		A/V Barrier & Roxul Ivl 3				<u> </u>	<u> </u>	<u> </u>		1	1										10-09	<u> </u>	
				Thu 20 10 01	Er: 20 10 00		1										Δ	/V Barrier &	Roxul Iv	13 -			
		A/V Barrier & Roxul Ivi 4	7 days 7 days	Thu 20-10-01 Wed 20-10-21			· · · ·				· ·			-			A	V Barrier &			& Roxul Ivl	<b>*</b>	10-29
							ļ ·											// Barrier &				<u>+</u>	10-29


0	Task Mode	Task Name	Duration	Start	Finish	04-05	04-19	Vlay 05-03	05-17	05-31	06-14	July 06-28	07-12	07-26	08-09	Sep 08-23	otember 09-06	09-20	10-04	10-18	lovember 11-01	11-15	1
	-,																						
_	-4	Construction	136 days		Mon 20-11-16	6	nstruction	05-06				;	i			·					i	11-16	
_		Mobilize foundation excavation	3 days 14 days		Wed 20-05-06 Wed 20-05-27	foundati	on excavati			05-27	<u>+</u>			+									·
		foundation	14 uays 10 wks		Wed 20-03-27 Wed 20-07-22			dation	·		<u> </u>	; <u> </u>	; <u> </u>	07-22	—				i — —	- — —	i		· i
	-	slab prep	3 wks		Wed 20-07-29			† —-' =	+-	+-		slab prep	-	07-29						+	+		·
	-,	place slabs SOG	1 wk	Thu 20-07-30	Thu 20-08-06			ī — -			<u> </u>		lace slabs S	og	08-06						- <u> </u>		·
	-,	Conc Beams	2 wks		Thu 20-08-06								ic Beams 🎽		08-06								
	-4	Hollow core slabs lvl 1	6 days	Fri 20-08-07				↓	$\perp$ —	<u> </u>	⊥ _	H	ollow core				-		I		↓		.
	-4	masonry lvl 1	7 days		7 Tue 20-08-25		·	<u> </u>			<u> </u>	<u> </u>	<u> </u>		ry Ivl 1	08-25	09-02		<u> </u>				
	-	hollow core slabs lvl 2	6 days		Wed 20-09-02	<u> </u>	—  —	+	+	+-	$\vdash$ $-$			nollow	core slabs ivi	nry Ivi 2	09-02			+	+		·
		masonry IvI 2 hollow core slabs IvI 3	7 days 6 days		Mon 20-09-14 Tue 20-09-22	<u> </u>	!		<u> </u>	<u> </u>	<u> </u>	<u> </u>		<u>+</u>	holl	nw core sla	bs Ivi 3	09-22	<u> </u>				- !
		masonry IvI 3	7 days		Thu 20-10-01			+	+	+	+-			+			masonry IvI 3		10-01				·
		hollow core slabs lvl 4	6 days	Fri 20-10-02			'	4 —— —	<u> </u>	<u> </u>	<u> </u>	· !					ollow core sla				!		· '
	-,	masonry IvI 4	7 days		2 Tue 20-10-20			1	+	+-	<u>+</u>			+				masonry		10-20			·
	-,	hollow core roof	7 days	Wed 20-10-2	Thu 20-10-29		·				1	· ·	·	· · · ·				holl	ow core roo	f 10	0-29		· ·
		met stud framing lvl 1	3 days		Tue 20-09-08									n	net stud fram						1		.
		met stud framing IvI 2	3 days	Wed 20-09-2		<u> </u>	—  —	+	+	+	<u> </u>			+	+	met stud	framing lvl			⊨	4	<u> </u>	·
	-	met stud framing IvI 3	3 days		2 Wed 20-10-14	<u> </u>	I	4	⊥	<u> </u>	∟		I	⊥	⊥	∟	met s		lvl 3 🐂 1 et stud fram		11-03		.
	-,	met stud framing Ivl 4 A/V Barrier & Roxul Ivl 1	3 days		Tue 20-11-03 Wed 20-09-16			+	+	+	<u>+</u>		+	+	A/V Barrior				et stud fran		+		·
		A/V Barrier & Roxul IVI 1 A/V Barrier & Roxul IVI 2	6 days 7 days		3 Tue 20-10-06	<u> </u>		+	+		<u> </u>			+	A V Darrier		rrier & Roxul		10-06	⊢ ₽	+		·
		A/V Barrier & Roxul Ivl 3	7 days	Thu 20-10-15		<u> </u>		+	+	+-	+-			+	+				xul Ivi 3	10-23	+	+	·
	-	A/V Barrier & Roxul Ivl 4	7 days	Wed 20-11-04		<u> </u>		+	+	<u>+</u>	<u>+</u>		+	+					A/V Barrier	& Roxul Ivi 4	<b>+</b> +	11-13	·
	-,	slab topping lvl roof	2 days		Mon 20-11-02			1	+	+-	-		1	+	+					j Ivi roof 🎽			·
					Thu 20 11 05			1			<u> </u>								slab	topping Ivl 4	11-05		
	-,	slab topping lvl 4	2 days	Wed 20-11-04																			
		slab topping lvl 3	2 days	Fri 20-11-06	Mon 20-11-09			↓												o topping Ivl			.
	-,			Fri 20-11-06 Tue 20-11-10				+ †	+ <u> </u>				1	‡ †						o topping IvI slab topping slab toppi	Ivi 2 🍆	1-12	·   ·
	-4 -4 -4	slab topping Ivl 3 slab topping Ivl 2	2 days 2 days	Fri 20-11-06 Tue 20-11-10	Mon 20-11-09 Thu 20-11-12			<u>↓</u> <u>†</u>						+ +						slab topping	Ivi 2 🍆	1-12	·   ·  =
t: ACL		slab topping IvI 3 slab topping IvI 2 slab topping IvI 1	2 days 2 days 2 days	Fri 20-11-06 Tue 20-11-10	Mon 20-11-09 Thu 20-11-12	nay		eadline titcal		Critic			Manual	Progress						slab topping	Ivi 2 🍆	1-12	


	Task	Tack Namo	Duration	Start	Finish	1			1				1.			1				1.			L
0	Mode	Task Name	Duration	Start	FINISN	03-22 04-05 04-19	May 05-03 05-1	7 05-31 (	July 6-14 06-28	07-12 07	-26 08-0	9 08-2	Septemb	06 09-20	10-04	10-18	November 11-01 1	1-15 11-29	12-13	January 12-27 0	1-10 01-24	02-07	March 02-21
2	-4	Construction	203 days	Mon 20.05	-0 Mon 21-02-22	Construction		<u> </u>		<u> </u>									<u> </u>			<u> </u>	02-22
		Mobilize	3 days		-0-Wed 20-05-06	Mobilize	05-06		— i — ·			- i		<u> </u>	i				$\dot{-}$		— i—	-	
ļ.	-	foundation excavation	14 days		07 Wed 20-05-27	foundation excavatio	n	05-27		++		-	- +-	+-		-+	+ -	_	+ +	+ -	_ _	+ +	
;	-	foundation	8 wks		L2 Wed 20-07-08	foundat				07-08					<u>ا                                     </u>								-
	-,	slab prep	3 wks		09 Wed 20-07-29			+ - +	slab prep		07-29	-		+ $-$	1	$\vdash$ +	+ -	_ _	+			+ $+$	
,		place slabs SOG	1 wk	Tue 20-07-2	28 Tue 20-08-04					abs SOG 📄													
3	-	Columns level 1	4 wks		-0!Tue 20-09-01			+ -+	Co	lumns level		-	09-01		1 1	$\vdash$ +	+ -	_	+		_	+ $+$	
1		SOD IvI 2	4 wks	Wed 20-08-	-2(Wed 20-09-23						SOD Iv			09									
0		Columns level 2	4 wks	Thu 20-09-1	17 Wed 20-10-14			$\top$				Column	ns level 2			10-14						$\top$ $\neg$	
1		SOD IvI 3	4 wks		08 Wed 20-11-04							_		SOD Iv			11-04		$\perp$			$\perp$	
2	-4	Columns level 3	4 wks		29 Thu 20-11-26				I					C	olumns le			11-26					
3	-4	SOD IVI 4	4 wks		) Thu 20-12-17	+ $+$ $ +$ $-$	I	+ $-+$		<u> </u>		_		+-	-	⊢ ⊣	SOD IVI 4		12-1			+ $-$	
4		Columns level 4	4 wks		1 Mon 21-01-11										!		Colur	nns level 4			01-11	02-01	
5		SOD roof	4 wks		05 Mon 21-02-01		I	+-+		+ +	$\rightarrow$ $-$	_	- +		-   <b> </b>	10-			SOD re	001		U2-U1	
6		met stud framing lvl 1	7 days		15 Fri 20-10-23	╞╾╶┷╶┷╴═┙						_ I	met s	tud framir					12-07				↓
7	-9	met stud framing lvl 2	7 days		7 Mon 20-12-07	+-+	I	+ $-+$		+ +		-	- +	-+	-	net stud	framing lv		12-07 stud framii		01-20	++	
18 19	-5	met stud framing IvI 3	7 days		L2 Wed 21-01-20							_				└─┤╶┦					ning Ivl 4	02-10	<u> </u>
20	-5	met stud framing Ivl 4 A/V Barrier & Roxul Ivl 1	7 days		02 Wed 21-02-10		-+-	+ $+$		+ +	$\rightarrow$ $-$	-		/V Barrier	& Royul I		11-02		+- <sup>me</sup>				
21		A/V Barrier & Roxul IVI 1 A/V Barrier & Roxul IVI 2	6 days 7 days		-2(Mon 20-11-02 08 Wed 20-12-16	<u>├</u> ── <del>│</del>	I					_ !						oxul Ivi 2	12-16	<u>-</u>	I	+	+
22		A/V Barrier & Roxul Ivl 3	7 days		21 Fri 21-01-29		I	+ - +		+ +	-+-	-	- +	+-		<u> </u>			V Barrier 8		3 - 0	1-29	
13		A/V Barrier & Roxul Ivl 4	7 days		11 Mon 21-02-22	<u> </u>		+		⊢ –⊢		-				⊢ →	+ -				r & Roxul I		02-22
oject: Ad			Milestone	*	Manual Tas		adline 4	k	Critical Split			Manual Pr	2²rogress =										


-	Task	Task Name	Duration	Start	Finish			May				July				Septembe	ər		L.	Vovember				Januar	v			March	
	Mode				-	03-22 04	4-05 0		03 05-17	05-31	06-14	06-28 (	07-12	07-26 08-	09 08	-23 09-06	6 09-20	10-04	10-18	11-01	11-15 1	1-29	12-13 1	2-27	y 01-10	01-24	02-07	02-21 03-07	03-21 04
_	->	Construction	224 days	Man 20.05 (	Tue 21-03-23	6	onstruc	tion					+								_ +			_					03-23
		Mobilize	3 days		Wed 20-05-06			bilize 👝 0	05-06	-i	i					- i				— i-	— i-					i — i			03-23
		foundation excavation	14 days		Wed 20-05-08	foundatio				05-27					_ _		+	+ -		-	-+			-					+
		foundation	14 days 10 wks		Wed 20-03-27 Wed 20-07-22			undation	N 7				0	7-22	—i—	— <u>i</u> —	<u> </u>	<u> </u>	- — i	— i-	— <u>i</u>					i — i	i — i	— <u> </u>	it —i ·
		slab prep	3 wks		Thu 20-08-13						1-1	slab pr			08-13		+	+			- +	- +	+-	-			+		+
		place slabs SOG	1 wk		Wed 20-08-05	-i				-i		place slab				— <u>;</u>	- <u>i</u>	<u> </u>	i — i	— i-	— <u>†</u>			-i		i — i	— ÷	— <u> </u>	
		SOD level 1	5 wks		Thu 20-09-10		- +-	+ -			<u> </u>		OD lev			- 0	9-10	+ -			- +	- +		-			+		++ -+ -
		Columns level 1	4 wks		Thu 20-10-01	$\vdash$			<u> </u>	- <u>i</u>	i i			Column	s level	14		10-01	<u> </u>	î	— <u>†</u>					i — i	i i		i i
	-,	SOD IVI 2	4 wks		Thu 20-10-22										_ _	SOD	vl 2		10-2	2	- +	- +		-			- +		+
		Columns level 2	4 wks		Fri 20-11-13	t i				- <u>`</u>	i i		- <u> </u>	- <u> </u>	—i—	c	olumns	level 2		<mark>_1</mark> 1	1-13					i — i	<u> </u>		$\overrightarrow{1}$
		SOD IvI 3	4 wks		Fri 20-12-04			+ -		_									SOD IVI 3		- +	12-0	4	-					
		Columns level 3	4 wks		Mon 20-12-28									·				<u> </u>	Ср	lumns				12-28					
	-4	SOD IvI 4	4 wks	Mon 20-12-2	Tue 21-01-19					_			_								s	OD IVI	4		0	01-19			
	-,	Columns level 4	4 wks	Wed 21-01-1	Tue 21-02-09	i i			<u> </u>					·	_;_		<u> </u>	<u> </u>		— i	<u></u>	Ço	olumns le	evel 4			02-0	9 1	
	-4	SOD roof	4 wks	Wed 21-02-0	Wed 21-03-03																				SOD	roof		03-03	
	-,	met stud framing lvl 1	7 days		Tue 20-11-24		1							·		- <u>_</u>	1	met stud	d framing			-24							
	-,	met stud framing lvl 2	7 days	Tue 20-12-29	Thu 21-01-07								+		_ _		+			m	et stud 1	framing	g Ivi 2 🎽		01-07	1—1			
	-,	met stud framing IvI 3	7 days		(Fri 21-02-19																		m	et stu		ing Ivl 3			
		met stud framing IvI 4	7 days	Thu 21-03-04	Fri 21-03-12																				me	t stud f	raming	lvi 4 🎽 0	3-12
		A/V Barrier & Roxul IvI 1	6 days	Wed 20-11-2	Wed 20-12-02						· · ·							A/V B	arrier &							· ·	+		
		A/V Barrier & Roxul IvI 2	7 days	Fri 21-01-08	Mon 21-01-18												<b>—</b> -				A/V Ba	rrier &	Roxul lv		0				
		A/V Barrier & Roxul IvI 3	7 days	Mon 21-02-2	Tue 21-03-02										_!_						- +			A/V	Barrie	r & Rox			
		A/V Barrier & Roxul Ivl 4	7 days	Mon 21-03-1	Tue 21-03-23																							Roxul Ivi 4 🍆	03-23
	-				100 21 05 25														II							A/V Ba	rrier & I		
	-9																									A/V Ba	rrier &		
	-9																									A/V Ba	rrier &		
	-9																									A/V Ba	rrier & I		
	-9																									A/V Ba	rrier &		
	<b>•</b> 9																									A/V Ba	rrier &		
																										A∕V Ba	rrier &		
	L Schedu		Milestone	<b>♦</b>	Manual Tas	k		Deadl	line	•		Critical Sp	plit			Manual Pro	pogress									A/V Ba	rrier & F		
		lle Concrete						Deadl		•		Critical Sp Progress				Manual Prc	ogress -									<u>А</u> /V Ва	rrier &		


**APPENDIX C – Structural Drawings** 











ALM . TURA - ALL FOOTINGS = 25 MPa AT 28 DAYS, CLASS OF EXPOSURE "N". 6 (7)(8) - SLAB-ON-GRADE = 25 MPa AT 28 DAYS, CLASS OF EXPOSURE "N". (NO FLY ASH TO BE USED IN MIX FOR SLAB). 12 (3) (4)(5) (9) (10) (11) (12) (13) (14) (15) (16) (17) - ALL FOUNDATION WALLS = 25 MPa AT 28 DAYS, CLASS OF EXPOSURE "C-2". (5% TO 8% AIR ENTRAINEMENT). - ALL EXTERIOR SLABS = 32 MPa AT 28 DAYS, CLASS OF EXPOSURE "C-2". 19'-0" 19'-0" 6'-0" 19'-0" 19'-0" 19'-0" 19'-0" 19'-0" 19'-0" 19'-0" 19'-0" 19'-0" 19'-0" 19'-0" 19'-0" 26'-0" 14'-0' 24'-0' 16'-0' TYP. AT PATIO 8'-0' 8'-0' TYP. AT PATIO 26'-0" 5" SLAB-ON-GRADE REINFORCED WITH 6x6 6/6 WWM.2" RIGID INSULATION AT U/S SLAB. TYP. T/SLAB EL. 105" - 0" U.N.O. 5" SLAB-ON-GRADE REINFORCED WITH 6x6 6/6 WWM. 2" RIGID INSULATION AT U/S SLAB. TYP. T/SLAB EL. 105" - 0" U.N.O. 2 1A|83 2.0° (A)ş (B) ISSUE DESCRIPTION ISSUED FOR PRICING DATE NOV. 19/19 **(c)** 틷 S1 81. (E 5" SLAB-ON-GRADE REINFORCED WITH 6x6 6/6 WWM. T/SLAB EL. 105" - 0" U.N.O. F  $\boxtimes$ 1 814|834 5 R (G) 2-0° TYP. (H)-5 8'-0" 8'-0" Job No. 18378 TYP. AT PATIO ieurs en structure 16'-0" Noncon NB E10 SYM TYP AT PATIO 14'-0" 24'-0" FLOOR DESIGN LOAD U.N.O. (SPECIFIED) 6'-0" LL = 40 paf U.N.O. LL = 100 paf (LORRIDOR, STAIRS, COMMUN AREAS AND BALCONIES) DL = SELF WEIGHT + 50 paf (NCLUDING MECHANICAL LOADS) DL = SELF WEIGHT + 12 paf (BALCONIES) FLOOR PLAN - LEVEL 1 SCALE: 1/16" = 1'-0" amp chitectural Designer Spi re DESIGN CD. 171 Lutz Street, Moncton, NB E1C 5E8 Bus: (506) 855-3777 Cell: (506) 312-2777 eMail Client

Project 55 Unit Residential No Paring Garage Wood Construction Drawing Title FLOOR PLAN - LEVEL 1 AND DETAILS

 Date
 November 19, 2019

 Oncoded by:
 JAR


 Down by:
 MH


 Revision


 Source:
 As indicated


 Bheat:
 S2A


 Flight no:






















- MORTAR FOR STRUCTURAL CONCRETE MASONRY BLOCK: TYPE S IN ACCORDANCE WITH CSA A179.

- MORTAR SHALL CONFORM TO CSA A179.

HORIZONTAL REINFORCEMENT: FOR SINGLE WYTHE CONCRETE BLOCK MASONRY: BL-10 LADDER REINFORCEMENT OR APPROVED ALTERNATE, HOT DIP GALVANIZED.

- BAR REINFORCEMENT: TO CSA A371 AND CSA G30.18, CARBON STEEL, GRADE 400 DEFORMED BARS.

MASONRY CONSTRUCTION NOTES: - STANDARD CONCRETE BLOCK UNITS: TO CSA A165 SERIES: CLASSIFICATION: FOR 8° CMU WALL: H/25/AM. - FOR 12° CMU WALL: H/30/A/M.



DATE


Job No. 18378


\*\*\*

no

set S6A

Flight no





## MASONRY CONSTRUCTION NOTES:

- STANDARD CONCRETE BLOCK UNITS: TO CSA A165 SERIES: CLASSIFICATION: - FOR 8' CMU WALL: H/30/A/M. - FOR 12' CMU WALL: H/30/A/M.

- BAR REINFORCEMENT: TO CSA A371 AND CSA G30.18, CARBON STEEL, GRADE 400 DEFORMED BARS. WIRE REINFORCEMENT: TO CSA A371 AND CSA G30.18, HIGH TENSILE STRENDTI STEEL WIRE, LADDER TYPE, HOT DIP GALVANIZED AFTER FABRICATION TO SATIA A153.


 HORIZONTAL REINFORCEMENT: FOR SINGLE WYTHE CONCRETE BLOCK MASORKY: BL-10 LADDER REINFORCEMENT OR APPROVED ALTERNATE, HOT DP GALVANUED. - MORTAR SHALL CONFORM TO CSA A179.


- MORTAR FOR STRUCTURAL CONCRETE MASONRY BLOCK: TYPE S IN ACCORDANCE WITH CSA A179.


- GROUT SHALL CONFORM TO CSA A179, TABLE 3. MINIMUM COMPRESSIVE STRENGTH OF GROUT TO BE 15 MPa AT 28 DAYS.





TURA














## MASONRY CONSTRUCTION NOTES:

 STANDARD CONCRETE BLOCK UNTS: TO CSA A165 SERIES: CLASSIFICATION: - FOR 8' GUIL WALL: H230/M FOR 12' CMJ WALL: H230/M FOR 12' CMJ WALL: H230/M -BAR REINFORCEMENT: TO CSA A371 AND CSA G30.18, CARBON STEEL, GRADE 400 DEFORMED BARS.


GRADE 400 DEFORMED BARS. - WIRE REINFORCEMENT: TO CSA A371 AND CSA G30.18, HIGH TENSILE STRENGTH STEEL WIRE, LADDER TYPE, HOT DIP GALVANIZED AFTER FABRICATION TO ASTM A153.


 HORIZONTAL REINFORCEMENT: FOR SINGLE WYTHE CONCRETE BLOCK MASONRY: BL-10 LADDER REINFORCEMENT OR APPROVED ALTERNATE, HOT DIP GALVANIZED.
 MORTAR SHALL CONFORM TO CSA A179.

- MORTAR FOR STRUCTURAL CONCRETE MASONRY BLOCK: TYPE S IN ACCORDANCE WITH CSA A179. - GROUT SHALL CONFORM TO CSA A179, TABLE 3. MINIMUM COMPRESSIVE STRENGTH OF GROUT TO BE 15 MPa AT 28 DAYS.









MASONRY CONSTRUCTION NOTES:

 STANDARD CONCRETE BLOCK UNTIS: TO CSA A169 SERES: CLASSFICATION: - FOR 6' CUM WALL: H230AM - FOR 12' CMJ WALL: H230AM.
 BAR REINFORCEMENT: TO CSA A371 AND CSA G30.18, CARBON STEEL, GRADE 440 DEFORMED BARS.

GRADE AUD DEPONIED BARS. - WIRE REINFORCEMENT: TO CSA A371 AND CSA G30.18, HIGH TENSILE STRENGTH STEEL WIRE, LADDER TYPE, HOT DIP GALVANIZED AFTER FABRICATION TO ASTM A153.


 HORIZONTAL REINFORCEMENT: FOR SINGLE WYTHE CONCRETE BLOCK MASONRY: BL-10 LADDER REINFORCEMENT OR APPROVED ALTERNATE, HOT DIP GALVANIZED.
 MORTAR SHALL CONFORM TO CSA A179.


MORTAR CHARLE COMPOUND CONFIRM STATEMENTS
 MORTAR FOR STRUCTURAL CONCRETE MASONRY BLOCK: TYPE S IN
 ACCORDANCE WITH CSA A179.

GROUT SHALL CONFORM TO CSA A179, TABLE 3.
 MINIMUM COMPRESSIVE STRENGTH OF GROUT TO BE 15 MPa AT 28 DAYS









## MASONRY CONSTRUCTION NOTES: - STANDARD CONCRETE BLOCK UNITS: TO CSA A165 SERIES: CLASSIFICATION: -FOR 8' CAU WALL: H/2/J/MA -FOR 8' CAU WALL: H/2/J/MA

- FOR 12 CMU WALL HIZDIAM. - FOR 12 CMU WALL HIZDIAM. - BAR REINFORCEMENT: TO CSA A371 AND CSA G30.18, CARBON STEEL, GRADE 400 DEFORMED BARS.


- WIRE REINFORCEMENT: TO CSA A371 AND CSA G30.18, HIGH TENSILE STRENGTH STEEL WIRE, LADDER TYPE, HOT DIP GALVANIZED AFTER FABRICATION TO ASTM A153.

- HORIZONTAL REINFORCEMENT: FOR SINGLE WYTHE CONCRETE BLOCK MASONRY: BL-10 LADDER REINFORCEMENT OR APPROVED ALTERNATE, HOT DIP GALVANIZED.

- MORTAR SHALL CONFORM TO CSA A179. - MORTAR FOR STRUCTURAL CONCRETE MASONRY BLOCK: TYPE S IN ACCORDANCE WITH CSA A179. - GROUT SHALL CONFORM TO CSA A179, TABLE 3. MINIMIA COMPRESSME STRENGTH OF GROUT TO BE 15 MPa AT 28 DAYS.










AL AN 11 R C.S. - COLUMN STRIP M.S. - MIDDLE STRIP T.U.L. - TOP UPPER LAYER T.L.L. - TOP LOWER LAYER )(2) (3) (4) (5) (6) (7) (8) 9 (10) (11) (12) (13) (14) (15) (16) (17) ĺ1 B.U.L. - BOTTOM UPPER LAYER B.L.L. - BOTTOM LOWER LAYER ← T.U.L. B.L.L. 6'-0" 19'-0" 19'-0" 19'-0" 19'-0" 19'-0" 19'-0" 19'-0\* 19'-0" 19'-0" 19'-0" 19'-0" 19'-0" 19'-0" 19'-0" BULL 26'-0\* 26'-0" 5" SLAB-ON-GRADE REINFORCED WITH 6x6 6/6 WWM. 2" RIGID INSULATION AT U/S SLAB. TYP. T/SLAB EL. 105" - 0" U.N.O. 7-6 7-6 5" SLAB-ON-GRADE REINFORCED WITH 6x6 6/6 WWM. 2" RIGID INSULATION AT U/S SLAB. TYP. T/SLAB EL. 105" - 0" U.N.O. 7-6" 7-6" 7-6 7-6 REINFORCING PLACEMENT 16'-0" TYP. AT PATIO 16'-0" 8'-0" TYP. AT PATIO 8'-0" 8'-0" A 힌문 5 (B) f. --6" HIGH BY 6" WIDE CONCRETE CURB. TYP. 2 5 1/2" 31/2 Ti DESCRIPTION SSUED FOR PRICING DATE NOV. 14/19 ISSUE (C) DE 20-15M T.U.L 20-15M T.U.L. 20-15M 10" STRUCTURAL SLAB T/SLAB EL: 105' - 0" 23'-8" 16-1\* M.S. T.U.L. 14-15M -15M B.L.L ╟╪╦╴ 9-15M BLL F  $\mathbf{X}$ 2 8181 2 811 ۶<u>h</u> ( G Z-0" (H) -0" 8'-0" TYP. AT PATIO Rev.# Date 16'-0" TYP. AT PATIO Job No. 18378 Ingénieurs en structure 14'-0" 24'-0" VALRON 100 rue Cameron St., Suite 5000 Moncton, NB E1C 5Y6 www.valron.ca Phone: 506.856.960 Fax: 506.854.682 Email: valron@valron.cc FLOOR PLAN - LEVEL 1 1 BEAM SCHEDULE SCALE: 1/16\* = 1'-0\* REINFORCING TYPE NOTE: REFER TO FIGURE 13.1 IN CSA A23.3-14 FOR STRUCTURAL SLAB BAR LENGTH SCHEDULE. 10" WIDE BY 1'-6" HIGH 2-25M TOP AND BOTTOM, 10M STIRRUPS AT 10" of 
 B2
 10" WIDE BY 1'-1 1/2" HIGH
 2-25M TOP AND BOTTOM, 10M STIRRUPS AT 10" old

 B3
 10" WIDE BY 1'-2 1/2" HIGH
 2-25M TOP AND BOTTOM, 10M STIRRUPS AT 10" old
 tamp FLOOR DESIGN LOAD U.N.O. (SPECIFIED) LL = 40 psf U.N.O. LL = 100 psf (CORRIDOR, STAIRS, COMMUN AREAS AND BALCONIES) DL = SELF WEIGHT + 50 psf (INCLUDING MECHANICAL LOADS) 8" 8" 10M TIES AT 10" c/c \*\*\* 2\* dl. TYP. 2-20M CONT. INTEGRITY BARS EACH WAY. SD no 7-25M BARS (BOTTOM) 8-25M VERTICAL BARS c/w 8-25M DOWELS -25M BARS (TOP) DESIGN CO. Street, Moncton, NB E1C 5E8 171 Lutz St Bus: (506) 855-3777 Cell: (506) 312-2777 eMa TYPICAL COLUMN DETAIL 2 SCALE: 3/4\* = 1'-0\* 55 Unit Residential o/w Parking Garage Concrete Construction Drawing Title INTEGRITY BARS DETAIL SCALE: 3/4" = 1'-0" FLOOR PLAN - LEVEL 1 SLAB REINFORCING DETAILS AT CORNER BEARING ON November 14, 2019 Date FOUNDATION WALLS 3 J hecked by: SL SCALE: 3/4\* = 1'-0\* Drawn by: MH Revision Scale: As indicated Sheet S2 Flight no:







(1)(2)(3) (4) (5) 6 (7)8 9 (10) (11) (12) (13) (14) (16) (17) (15) 6'-0" 19'-0" 19'-0" 19'-0" 19'-0\* 19'-0" 19'-0" 19'-0" 19'-0" 19'-0" 19'-0" 19'-0" 19'-0" 19'-0" 19'-0" 6'-0" 26'-0" 26'-0" 5" SLAB-ON-GRADE REINFORCED WITH 6x6 6/6 WWM. 2" RIGID INSULATION AT U/S SLAB. TYP. T/SLAB EL. 105" - 0" U.N.O. 7-6 7-6 7-6\* 7-6\* 7-6\* 7-6\* 7-6\* 7-6\* 7-6\* 7-6\* 1 16'-0" 5" SLAB-ON-GRADE REINFORCED WITH 6x6 6/6 WWM. 2" RIGID INSULATION AT U/S SLAB. TYP. T/SLAB EL. 105" - 0" U.N.O. I TYP. AT PATIO 8'-0" 8'-0" TYP. AT PATIO (A)20°C --<u>†</u>--(B) -----\_ 6" HIGH BY 6" WIDE CONCRETE CURB. TYP. 2 \$2A -6.1/2" -6.1/2" (C) \_\_\_\_\_ \_\_\_\_ \_0\_ 5" SLAB-ON-GRADE REINFORCED WITH 6x6 6/6 WWM. T/SLAB EL. 105' - 0" U.N.O. (E)



8'-0" TYP. AT PATIO

TYP. AT PATIO

24'-0

16'-0"

14'-0"

BEAM SCHEDULE			
TYPE	SIZE	REINFORCING	
B1		2-25M TOP AND BOTTOM, 10M STIRRUPS AT 10" c/c	
B2	10" WIDE BY 1'-1 1/2" HIGH	2-25M TOP AND BOTTOM, 10M STIRRUPS AT 10" c/c	
B3	10" WIDE BY 1'-2 1/2" HIGH	2-25M TOP AND BOTTOM, 10M STIRRUPS AT 10" c/c	

2 81A 83A


- \*

 FLOOR DESIGN LOAD U.N.O. (SPECIFIED)

 LL = 40 pdf U.N.O.

 LL = 500 pdf (CORRIDOR, STAIRS, COMMUN AREAS AND BALCONIES)

 DL = 56LF WEIGHT = 50 pdf (INCLUDING MECHANICAL LOADS)



2 81A/S1A

> 2'.0' TYP.

3 1A 53A


-

(F

(G)

(H)





-h





TIR

55 Unit Residential No Parking Garage Concrete Construction Drawing Title

FLOOR PLAN - LEVEL 1

Date Novembe	r 14, 2019
Checked by: SL	
Drawn by: MH	Revision
Scale: As indicated	
Sheet S2A	Flight no:

